

SURVEY & RECONSTRUCTION
 SEP 13 1995
 COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
 KENT COUNTY

(County)	Located In:	Corner Code #
1. Public Land Survey	T 8N R 12W	E-7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 95 JUN 29 AM 11:52
 REG. OF DEEDS
 448

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Kirk Breitels, in a field survey on Feb. 15, 1995
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-7	1838 GLO	Whitcomb	Set Post
	1894-1969 Williams & Works		Leaded Stone-"T" Iron
	1974 Kent Co. Wit.		Mon. Box
	1985 LCRC #4330	Bueche	Set Kent County Monument in mon. box

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 11/27/85 and was recorded per LCRC #4330

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-7 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the 3/4" Iron he found inside a mon. box. Said Iron checks with Kent Co. Wit. and Williams & Works information.

LCRC #4330

KC Remon. tag & nail W. side 14" Maple	N18°E	81.05'
KC Remon. tag & nail in P. Pole	S55°W	71.95'
NE cor. of catch basin at back of curb	N26°E	56.28'
"X" cut in conc. curb	N28°W	48.70'
"X" cut in conc. curb	S34°E	47.38'
"X" cut in conc. curb	S23°W	58.25'

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 6/22/95
 CHAIRMAN *Harry Kube*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-7 Standard Kent County Monument

New KC Remon. tag & nail W. side 18" Maple	N18°E	80.87'
KC Remon. tag & nail in P. Pole	S55°W	71.95'
NE cor. of catch basin at back of curb	N26°E	56.28'
"X" cut in conc. curb	N28°W	48.20'
"X" cut in conc. curb	S34°E	47.38'
"X" cut in conc. curb	S23°W	58.25'



Signed by *Kirk Breitels*
 Surveyor's Michigan License No. 30077

Date 6/22/95