

\$7.00 SEP 18 1995
\$2.00 COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in KENT COUNTY (County)	Located In:	Corner Code #
1. Public Land Survey	T 8N R 12W	F-1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Section	S T R	
	S T R	

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
95 JUN 29 AM 11:53
REG. OF DEEDS
Luis Bond
8454

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, Kirk Breitels, in a field survey on March 2, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-1	1838	GLO		Not Set
	1966	Kent Co. Wit.		Iron in mon. box
	1984	LCRC #4086	Kolehouse	Set Kent County Monument
	1991	LCRC #6114	By	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Randy J. Kolehouse on 11/17/84 and was recorded per LCRC #4086

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-1 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Randy J. Kolehouse on twp. line in place of the 1" Iron in a mon. box he found. Said Iron in mon. box checks with Kent Co. Wit. and C.P. Co. information.
LCRC #6114 (some of same witnesses LCRC #4086)

NE cor. NE C.P. tower leg at grade	South	36.46'	
NW cor. NW C.P. tower leg at grade	S30°W	40.87'	P.A. 345 1990 KENT COUNTY
Chiseled "X" on E. end 12" conc. drwy. culv.	S50°E	47.67'	PEER APPROVED 6/22/95
NE cor. (siding) Hse. #2812	S55°W	119.13'	
KC Mon. at S 1/4 cor. Sec. 33, T9N, R12W	West	152.01'	CHAIRMAN <i>Harry Kube</i>

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-1 Standard Kent County Monument			
NE cor. NE C.P. tower leg at grade	South	36.46'	
NW cor. NW C.P. tower leg at grade	S30°W	40.87'	
Chiseled "X" on E. end 12" conc. drwy. culv.	S50°E	47.67'	
NE cor. (siding) Hse. #2812	S55°W	119.13'	
KC Mon. at S 1/4 cor. Sec. 33, T9N, R12W	West	151.96'	



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 6/22/95