

RECORDING & DOCUMENTATION

\$7.00
\$2.00

JAN 24 1996

KENT COUNTY REMONUMENTATION

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located In:

Corner Code #

| | | | | | |
|--------------------------------------|---|----|---|-----|-----|
| 1. Public Land Survey | T | 8N | R | 12W | F-2 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | T | R | | |
| | S | T | R | | |
| 3. Miscellaneous Property in Section | S | T | R | | |
| | S | T | R | | |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

REG. OF DEEDS

Lucy Bond

95 DEC 20 AM 8:36

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

8766

Register of Deeds Stamp & File Number

I, Kirk Breitels, in a field survey on Sept. 7, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

F-2 1837 GLO Not Set
1910 Williams & Works Set Stone

No other information for this corner

P.A. 345 1990 KENT COUNTY
PEER APPROVED 9/28/95
CHAIRMAN *Stan Huber*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-2 Found "T" Iron (bent) with stones around, 0.4' S. & 0.1' E. of intersection of 1/4 lines.

The "T" Iron is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-2 Set Standard Kent County Monument in place of "T" Iron.
 Set Nail & KC Remon. tag N. side 10" Thornapple N85°W 42.29'
 C/L Nut & Bolt E. side SE leg (holds diagonal brace)
 of CP tower N05°W 55.44'
 N 1/4 corner (Kent Co. Mon.) Sec. 4 North 2904.86'
 S 1/4 corner (Kent Co. Mon.) Sec. 4 South 2640.08'
 E 1/4 corner (Kent Co. Mon.) Sec. 4 East 2606.29'
 W 1/4 corner (Kent Co. Mon.) Sec. 4 West 2600.90'



Signed by *Kirk Breitels*

Date 12/6/95

Surveyor's Michigan License No. 30077