

KENT COUNTY REMONUMENTATION

JAN 24 1996

\$7.00  
\$2.00

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
KENT COUNTY  
(County)

Located In:

Corner Code #

1. Public Land Survey	T	<u>8N</u>	R	<u>12W</u>	<u>F-8</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T		
	S		T		
3. Miscellaneous Property in Section	S		T		
	S		T		

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

95 DEC 20 AM 8:37

REG. OF DEEDS  
*Lucy Bond*

8781

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kirk Breitels, in a field survey on Sept. 1, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- F-8 1837 GLO Not Set
- 1957-59 Williams & Works "Center of Sec. 2651.85' North of S 1/4 cor."
- 1969 Consumers Power Co. "T" Iron
- 1977 Survey McCloskey "Center" of Sec. 21

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-8 Found nothing at the C 1/4 corner area except remains of fence (buried) East & West. Computed intersection of 1/4 lines for C 1/4 corner fits angles and measurements of 1977 McCloskey survey by 00°00'10"± and 0.5'±. Prorated measurements agree with those of Consumers Power Co. survey. Measured 2652.32' North of S 1/4 cor. - 2651.85' Williams & Works 1957.

The Intersection of 1/4 lines is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 9/28/95  
CHAIRMAN *Harry Huber*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- F-8 Set Standard Kent County Monument at the intersection of 1/4 lines.
- Set Nail & KC Remon. tag SW side 10" Cherry S40°E 45.83'
- Set Nail & KC Remon. tag SW side 10" Apple N45°W 52.67'
- C/L top bolt, E. side, SE corner CP Co. tower (at bottom of leg for diagonal brace) N10°W 130.93'
- Set Nail & KC Remon. tag SE side 10" Apple N65°E 64.17'



Signed by *Kirk Breitels*

Date 12/6/95

Surveyor's Michigan License No. 30077