

OCT 28 1994

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 94 AUG 24 AM 11:52

For corners in Kent (County)

Located In: Alpine Twp. Corner Code =#

- | | | |
|------------------------------------|--------------------------|---------------------|
| 1. Public Land Survey | T <u>8N</u> R <u>12W</u> | F-12 |
| | T _____ R _____ | cen. sec. <u>33</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling In Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Wallace E. Glaza
 REG. OF DEEDS

6971

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		▲		34		35		36		
13													

I, Wallace E. Glaza, in a field survey on August 10, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Williams and Works

- 1945 - Found and accepted conc. mon. at center of Section
 - 1) Fence post NE 36.5'
 - 2) Fence post E 28.5'
 - 3) Fence post SW 35.10'
- 1952 - Found and accepted conc. mon. at center of Section
- 1956 - Found and accepted conc. mon. at center of Section
- 1964 - Found and accepted bolt spike at center by witnesses
- 1966 - Found and accepted iron at center of Section
- 1968 - Found and accepted conc. mon. at center of Section

- L.C.R.C. No. 289 (MVK)
- Found 3/4" iron at corner
 - 1) Nail in side T-pole NW 28.71'
 - 2) Nail in side 16" pine ESE 40.71'
 - 3) Nail in side T-pole SSE 160.04'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-12 (Center of Section 33, T8N, R12W, Alpine Township, Kent County, Michigan)

Found bolt spike over 1" rerod over conc. monument. Existing location is 7.64' North and 4.39' West of intersection of 1/4 lines. Verified location by old angles and distances. Accepted existing location for center. Replaced spike, rerod and conc. monument with standard 4" x 20" Kent County Monument. (Harrison)


- West 1/4 corner to center - 2657.03'
- North 1/4 corner to center - 2639.53'
- East 1/4 corner to center - 2575.77'
- South 1/4 corner to center - 2574.57'

P.A. 345.1990 KENT COUNTY
 PEER APPROVED 7/28/94
 CHAIRMAN *Hampsher*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-12 (4" x 20" Kent County Monument)

- | | | |
|---|-------|--------|
| 1) Remon tag & nail in S. side 18" pine | N70°W | 35.99' |
| 2) Remon tag & nail in N. side 18" pine | S70°E | 40.63' |
| 3) Remon tag & nail in NE side 12" elm | S25°E | 82.58' |
| 4) Remon tag & nail in SE side 18" elm | S35°W | 48.76' |
| 5) On centerline North-South road | | |
| 6) Iron pipe | West | 32.86' |



Signed by Wallace E. Glaza Date 8-16-94
 Surveyor's Michigan License No. 31592