

SURVEYS
REMONUMENTATION

\$7.00
\$2.00 SEP 18 1995
COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located In: _____ Corner Code # _____

- 1. Public Land Survey T 8N R 12W F-13
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Section S _____ T _____ R _____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
95 JUN 29 AM 11:54
REG. OF DEEDS
Lucy Sand
8460
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2						
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, Kirk Breitels, in a field survey on March 23, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-13	1837	GLO	Brookfield	Set Post
		Williams & Works		Stone
		Kent Co. Wit.		Iron in blacktop
	1972	LCRC #289	VanKooten	1" Iron
	1981	LCRC #1784	Merdzinski	Set Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 1/20/81 and was recorded per LCRC #1784

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-13 Found PK Nail in the same position as the standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set in 1981 by John A. Merdzinski in place of the 1" Iron over a stone he found. Said Iron and Stone check with Kent Co. Wit. and LCRC #289.

LCRC #1784

Nail & KC Remon. tag E. side 18" Pine	N20°E	124.42'
Nail & KC Remon. tag SE side T. Pole	N60°E	53.30'
Nail & KC Remon. tag S. side P. Pole	S55°E	121.81'
Nail & KC Remon. tag SE side Light Pole	S40°W	46.57'
Nail & KC Remon. tag NW side P. Pole	S50°W	91.42'
Nail & KC Remon. tag SW side 16" Maple	N55°W	76.67'

P.A. 345 1990 KENT COUNTY
PEER APPROVED 6/22/95
CHAIRMAN Harry Fisher

C/L Rd. N-S is 7' W.; C/L Rd. E-W is 1.5' N.; Iron West 18.00'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13 Set Standard Kent County Monument in place of the PK Nail

New Nail & KC Remon. tag E. side 27" Pine	N20°E	124.24'
Nail & KC Remon. tag S. side P. Pole	S55°E	121.83'
NW corner brick house	S20°E	146.14'
Set Nail & KC Remon. tag SW side Tel. Pole	N55°W	71.19'
Set Nail & KC Remon. tag NW side P. Pole	S55°W	91.54'
Kent Co. Mon. (F-1, T7N, R12W)	East	18.01'



Signed by Kirk Breitels

Date 6/22/95

Surveyor's Michigan License No. 30077