

\$7.00
\$2.00

SEP 10 1995

COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 8N R 12W G-2
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Section S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 95 JUN 29 AM 11:54
 REG. OF DEEDS
Lucy Jones
 8462

Register of Deeds Stamp & File Number

I, Kirk Breitels, in a field survey on June 1, 19 95

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management, or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G-2 1838 GLO Whitcomb Set Post
- 1888 Williams & Works Leaded Stone
- Kent Co. Wit. Leaded Stone
- 1916 Williams & Works Fence Post in place of stone ?
- 1986 LCRC #4412 Bueche Set Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 4/14/86 and was recorded per LCRC #4412.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-2 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the Leaded Stone he found by the intersection of fences. Said Leaded Stone checks with Kent Co. Wit. and Williams & Works information

LCRC #4412

- KC Remon. tag & nail N. side 24" Maple N85°E 20.98'
- KC Remon. tag & nail NW side 8" Oak S30°W 18.75'
- KC Remon. tag & nail S. side W. Cherry S85°W 15.27'
- KC Remon. tag & nail E. side 10" Oak N00°E 37.53'
- KC Remon. tag & nail E. side 10" Oak N25°E 45.25'


P.A. 345 1990 KENT COUNTY
 PEER APPROVED 6/22/95
 CHAIRMAN *Harry Bueche*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-2 Standard Kent County Monument

- New KC Remon. tag & nail N. side 27" Maple N85°E 20.98'
- New KC Remon. tag & nail SE side 15" Oak S30°W 19.01'
- New KC Remon. tag & nail S. side 10" W. Cherry S85°W 15.27'
- New KC Remon. tag & nail E. side 12" Oak N00°E 37.60'
- Set KC Remon. tag & nail NW side 8" Elm N45°E 2.71'



Signed by *Kirk Breitels*

Date 6/22/95

Surveyor's Michigan License No. 30077