

\$7.00
\$2.00

SEP 13 1985

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>12W</u>	<u>G-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

95 JUN 29 AM 11:54

REG. OF DEEDS
Lucy S. ...
8471

Register of Deeds Stamp & File Number

I, Kirk Breitels, in a field survey on Feb. 13, 19 95

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-11	1838	GLO	Whitcomb	Set Post
	1943	Kent Co. Wit.		Conc. Mon.
	1971	LCRC #71	VanKooten	3/4" Iron
	1977	LCRC #972	Merdzinski	"T" Iron top of 3/4" Iron
	1981	LCRC #2388	Bueche	Set Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 12/3/81 and was recorded per LCRC #2388.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-11 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the "T" iron over a conc. mon. he found. Said "T" Iron and conc. mon. check with Kent Co. Wit. and LCRC's #71 & #972.

LCRC #2388

KC Remon. tag & nail S. side 8" Elm	S40°E	99.36'
KC Remon. tag & nail W. side 14" Apple	N50°E	99.10'
KC Remon. tag & nail S. side 10" Ash	N40°W	75.34'
KC Remon. tag & nail S. side 18" Ash	N85°W	69.83'
KC Remon. tag & nail SE side 12" Elm	S55°W	64.12'
"X" cut S. end conc. culv.	S75°E	65.45'

P.A. 345 1980 KENT COUNTY
PEER APPROVED 6/22/95
CHAIRMAN *Harry ...*

on C/L blktp N-S; on C/L grav. East

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-11 Standard Kent County Monument

New KC Remon. tag & nail S. side 14" Ash	N40°W	75.32'
New KC Remon. tag & nail S. side 24" Ash	N85°W	69.64'
S. end 15" CMP culv.	S65°E	68.97'
N. end 15" CMP culv.	N75°E	69.22'
Set KC Remon. tag & nail SE side 24" Beech	S45°W	100.64'
on C/L blktp N-S; on C/L blktp. East		



Signed by Kirk Breitels Date 6/22/95
Surveyor's Michigan License No. 30077