

\$7.00  
\$2.00

JAN 24 1996

KENT COUNTY REMONUMENTATION

COMMISSION LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
KENT COUNTY  
(County)

Located In:

Corner Code #

1. Public Land Survey	T	8N	R	12W	H-2
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

REG. OF DEEDS

8765

95 DEC 20 AM 8:36

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Sept. 6, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4				3		2			1
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

H-2 1837 GLO Not Set  
 1944 Kent Co. Wit. Iron on Stone  
     36" Elm NW 53.15'  
     Ctr. 6" Apple WSW 88.4'  
     T.P. SSE 71.7'  
     Ctr. 6" Apple SW 77.3'  
 1991 Survey Roosien Ran N-S 1/4 line between 1/4 corners.

P.A. 345 1990 KENT COUNTY

PEER APPROVED 9/28/95

CHAIRMAN *Harry Huber*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-2 Found nothing at corner nor do any witnesses from 1944 Kent Co. Wits remain. Established intersection of 1/4 lines and found to be on line with brush and tree row to West. C/L Asph Road is West 3'±. Found Capped Rerod (All Points) 32.93' West.

The Intersection of 1/4 lines is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-2 Set Standard Kent County Monument at the Intersection of 1/4 lines.  
 Capped Rerod (All Points) West 32.93'  
 Set Nail & KC Remon. tag NW side 4" Apple S60°W 40.77'  
 Set Nail & KC Remon. tag NE side Tw. 6" Poplar N35°W 46.54'  
 Cut "X" top E. end large E-W conc. culv. N25°E 60.65'  
 C/L top MBT box (E'ly of 2) N50°E 34.36'



Signed by *Kirk Breitels*

Date 12/6/95

Surveyor's Michigan License No. 30077