

\$7.00
\$2.00

SEP 18 1995

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>12W</u>	<u>H-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

95 JUN 29 AM 11:55

REG. OF DEEDS

Register of Deeds Stamp & File Number

I, Kirk Breitels, in a field survey on Feb. 15, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3							●					
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-3	1838	GLO	Whitcomb	Set Post
	1880	Williams & Works		Original post
	1934	Kent Co. Wit.		Hole in stone
	1985	LCRC #4333	Bueche	Set Kent County Monument
	1990	LCRC #5382	Starr	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 10/17/85 and was recorded per LCRC #4333.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-3 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the Rerod he found over a stone with a hole in it. Said Rerod checks with Kent Co. Wit.

LCRC # 4333 & #5382

"X" cut S. end conc. culvert	S80°W	71.12'
"X" cut N. end conc. culvert	N70°W	76.22'
Nail & KC Remon. tag NW side (6' high) P. Pole	S50°W	154.41'
SW corner of MBT box	N60°E	64.65'
Nail & KC Remon. tag SW side P. Pole	S50°E	128.82'
On centerline blacktop N-S & E, centerline blacktop W. is 6' N.		

P.A. 345 1990 KENT COUNTY
PEER APPROVED 6/22/95
CHAIRMAN *Harry Bueche*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-3 Standard Kent County Monument		
"X" cut S. end conc. culvert	S80°W	71.12'
"X" cut N. end conc. culvert	N70°W	76.13'
Nail NW side (6' high) P. Pole	S50°W	154.39'
SW corner of MBT box	N60°E	64.65'
Nail & KC Remon. tag SW side P. Pole	S50°E	128.82'
On centerline blacktop N-S & E, centerline blacktop W. is 6' N.		



Signed by *Kirk Breitels*

Date 6/22/95

Surveyor's Michigan License No. 30077