

\$7.00
\$2.00 SEP 1 1995

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located In:	Corner Code #
T 8N R 12W	H-7
T R	
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
95 JUN 29 AM 11:55
REG. OF DEEDS
8476

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Kirk Breitels, in a field survey on Feb. 20, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-7	1838	GLO	Whitcomb	Set Post
	1969	Kent Co. Wit.		1" Iron in mon. box
	1980	LCRC #1363	Stadt	Set PK and tag from prev. survey data
	1983	LCRC #3616	Bueche	Set Kent County Monument
	1990	LCRC #5384	Starr	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 10/28/83 and was recorded per LCRC #3616.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-7 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the PK Nail he found. Said PK Nail checks with LCRC #1363. Corner per Kent Co. Wit. is incorrect.

LCRC #3616 & #5384

"X" cut in conc. curb	N60°E	45.30'
"X" cut in conc. curb	S30°E	43.60'
"X" cut in East end conc. culv.	N30°E	68.73'
PK in curb joint	S60°W	47.18'
SE cor. conc. slab 5' x 2' MBT box	N30°W	64.43'
On C/L blacktop road N-S & E-W		

P.A. 345 1990 KENT COUNTY
PEER APPROVED 6/22/95
CHAIRMAN Harry Huber

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-7 Standard Kent County Monument		
"X" cut in conc. curb	N60°E	45.30'
"X" cut in conc. curb	S30°E	43.60'
"X" cut in East end conc. culv.	N30°E	68.73'
SE cor. conc. slab 5' x 2' MBT box	N30°W	64.43'
"X" cut in conc. curb	S50°W	43.69'
On C/L blacktop road N-S & E-W		



Signed by Kirk Breitels Date 6/22/95
Surveyor's Michigan License No. 30077