

JAN 24 1996

KENT COUNTY REMONUMENTATION

\$7.00
\$2.00

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located In:

Corner Code #

1. Public Land Survey	T	8N	R	12W	H-10
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

REG. OF DEEDS

W. J. Spauld

95 DEC 20 AM 8:38

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

8788

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kirk Breitels, in a field survey on Sept. 6, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- H-10 1837 GLO Not Set
- 1912 Williams & Works Set Stone at "X" 1/4 lines.
- 1960 Kent Co. Wit. 1" Iron in Mon. Box
- 36" Elm SW 42.52'; 24" Elm NW 85.09'
- 1962-68 Williams & Works Mon. Box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-10 Found 1" Iron Pipe in Mon. Box 2.6' W. & 2.3' N. of intersection of 1/4 lines. No witnesses from any source remain. Iron in Mon. Box fits surveys by MVK (1978).

The 1" Iron Pipe in Mon. Box is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

P.A. 345 1990 KENT COUNTY

PEER APPROVED 9/28/99

CHAIRMAN *Harry Huber*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- H-10 Set Standard Kent County Monument in Mon. Box in place of the 1" Iron Pipe
- Top C/L MBT Pedestal S30°W 29.15'
- W. cor. of base to MBT box S50°E 101.08'
- Set Nail & KC Remon. tag N. side 15" Poplar S80°E 152.71'
- C/L 3" orchard tree N55°E 76.6'
- Face of N'yly steel sign post S90°W 14.62'



Signed by *Kirk Breitels*

30077

Date 12/6/95

Surveyor's Michigan License No. _____