

SEP 18 1995

KENT COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in KENT COUNTY (County)

Located In:

Corner Code #

1. Public Land Survey	T	8N	R	12W	H-13
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous	S		T	R	
Property in Section	S		T	R	

95 AUG 29 AM 10:39  
 REGISTERED FOR RECORD  
 COUNTY OF KENT  
 STATE OF MICHIGAN  
 REG. OF DEEDS 8698  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kirk Breitels, in a field survey on July 5, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-13	1837	GLO	Brookfield	Set Post
		Kent Co. Wit.		1" Iron over stone
	1971	LCRC #76	Chambers	1 1/2" Iron in mon. box
	1980	LCRC #1453	Merdzinski	Set Kent County Monument in mon. box
	1990	LCRC #5387	Starr	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 10/27/80 and was recorded per LCRC #1453

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the 1 1/2" Iron he found inside a mon. box. Said Iron checks with Kent Co. Wit. and LCRC #76.

LCRC #1453 & 5387

Nail & KC Remon. tag W. side P. Pole	S45°W	67.28'
Nail & KC Remon. tag S. side 30" Maple	S75°W	84.12'
Nail & KC Remon. tag S. side 16" Walnut	N70°W	103.93'
Nail & KC Remon. tag E. side 10" Pine	N16°W	143.13'
SE corner of storage building	N49°W	109.46'
E. leg of sign	S06°W	15.63'

P.A. 345 1990 KENT COUNTY  
 PEER APPROVED 8/24/95  
 CHAIRMAN Harry Huber

C/L blacktop road E-W; on C/L blacktop road North

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13 Standard Kent County Monument

Set Nail & KC Remon. tag SE side P. Pole	S50°W	67.28'
New Nail & KC Remon. tag S. side 24" Walnut	N70°W	103.86'
New Nail & KC Remon. tag E. side 14" Pine	N16°W	143.12'
SE corner of storage building	N49°W	109.34'
Face of E. leg of sign	S06°W	15.95'
Set Nail & KC Remon. tag W. side Lt. Pole	S00°W	22.12'
Kent County Monument (H-1, T7N, R12W)	East	30.62'

C/L blacktop road E-W; on C/L blacktop road North



Signed by Kirk Breitels

Date 8/24/95

Surveyor's Michigan License No. 30077