

\$7.00  
\$2.00  
SEP 18 1995

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
KENT COUNTY  
(County)

Located In:

Corner Code #

1. Public Land Survey	T	<u>8N</u>	R	<u>12W</u>	I-1
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Section	S	_____	T	_____	R
	S	_____	T	_____	R

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
95 JUN 29 AM 11:55  
REG. OF DEEDS  
*Lucy J. Bond*  
8479  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, Kirk Breitels, in a field survey on Jan. 25, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-1	1838	GLO	Whitcomb	Set Post
	1949	Kent Co. Wit.		Mon. Box
	1955	Williams & Works		Mon. Box
	1984	LCRC #4089	Kolehouse	Set Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Randy J. Kolehouse on 11/17/84 and was recorded per LCRC #4089

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-1 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Randy J. Kolehouse on township line in place of the Boat Spike he found, 1.48' South of an Iron in a mon. box. Iron in mon. box checks with Kent Co. Wit. & Williams & Works LCRC #4089

Nail & KC Remon. tag E. side P. Pole	S20°W	54.98'
Nail & KC Remon. tag SE side P. Pole	N45°E	47.77'
SE cor. frame house	N40°W	38.62'
SE cor. frame house	N10°E	53.94'
Iron in mon. box	North	1.48'
KC mon. at SE cor. Sec. 34, T9N, R12W	West	60.45'

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 6/22/95  
CHAIRMAN *Randy Kolehouse*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner

I-1 Standard Kent County Monument

Nail & KC Remon. tag E. side P. Pole	S20°W	54.94'
Nail & KC Remon. tag SE side P. Pole	N45°E	47.67'
SE cor. frame house	N40°W	38.62'
SE cor. frame house	N10°E	53.76'
Iron in mon. box	North	1.58'
KC mon. at SE cor. Sec. 34, T9N, R12W	West	60.38'



Signed by *Kirk Breitels* Date 3/20/95  
Surveyor's Michigan License No. 30077