

\$7.00  
\$2.00  
SEP 1 8 1995

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
KENT COUNTY

	Located In:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>12W</u>	<u>I-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
95 JUN 29 AM 11:55  
REG. OF DEEDS  
*Lucy Stand*  
8480  
Register of Deeds Stamp & File Number

I, Kirk Breitels, in a field survey on Feb. 6, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-2	1838	GLO	Whitcomb	Set Post
	1944	Kent Co. Wit.		Iron on leaded stone
	1981	LCRC #1898	Hay	Set Rerod & cap after const.
	1982	LCRC #3083	Merdzinski	Set Kent County Monument
	1990	LCRC #5388	Starr	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 8/2/83 and was recorded per LCRC #3083.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-2 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the Capped Iron he found. Said Capped Iron checks with Kent Co. Wit. and LCRC #1898.

LCRC #3083 & #5388

Nail & KC Remon. tag N. side P. Pole	S60°W	56.42'
Nail & KC Remon. tag N. side 17" Apple	N65°E	56.40'
Nail & KC Remon. tag N. side 4" Walnut	East	45.56'
Nail & KC Remon. tag W. side 6" Walnut	S25°E	72.75'
SE cor. steel building	S40°W	117.15'
On C/L blacktop road North & South		

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 6/22/95  
CHAIRMAN *Harry Kube*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-2 Standard Kent County Monument		
Nail & KC Remon. tag N. side P. Pole	S60°W	56.49'
New Nail & KC Remon. tag W. side 8" Walnut	S25°E	72.81'
Set Nail & KC Remon. tag S. side P. Pole	N70°E	44.06'
Set Nail & KC Remon. tag NE side 40" Pine	N45°W	98.16'
SE cor. steel building	S40°W	117.15'
On C/L blacktop road North & South		



Signed by *Kirk Breitels* Date 6/22/95  
Surveyor's Michigan License No. 30077