

\$7.00  
\$2.00  
SEP 1 1995

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
KENT COUNTY

(County)	Located In:	Corner Code #
1. Public Land Survey	T 8N R 12W	I-10
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
95 JUN 29 AM 11:56  
REG. OF DEEDS OO  
*Lucy St...*

Register of Deeds Stamp & File Number

I, Kirk Breitels, in a field survey on March 1, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- I-10 1838 GLO Whitcomb Set Post
- 1914-54 Williams & Works Stone-Iron-RR Spike
- 1935 Kent Co. Wit. Iron & Stone
- 1967 Kent Co. Wit. RR Spike
- 1986 LCRC #4222 Bueche Set Kent County Monument
- 1990 LCRC #5396 Starr Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 6/15/86 and was recorded per LCRC #4222.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-10 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the RR Spike he found. Said RR Spike checks with Kent Co. Wit. and Williams & Works information.

LCRC #4222 & #5396

- SW corner brick house N55°E 150.87'
- NE corner conc. porch S45°W 112.56'
- Nail & KC Remon. tag NE side P. Pole S50°E 70.86'
- Nail & KC Remon. tag E. side Serv. Pole S25°W 73.36'
- Nail & KC Remon. tag E. side 10" Apple N55°W 74.60'
- Nail & KC Remon. tag N. side Tele. Pole N65°E 68.25'

P.A. 345 1990 KENT COUNTY

PEER APPROVED 6/22/95  
CHAIRMAN Harry Huber

On C/L E. & W. bit. road (Alpine Church); C/L N. & S. bit. road is 2' East

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-10 Standard Kent County Monument

- SW corner brick house N55°E 150.87'
- NE corner conc. porch S45°W 112.56'
- Nail & KC Remon. tag NE side P. Pole S50°E 70.92'
- Nail & KC Remon. tag E. side Serv. Pole S25°W 73.41'
- Set Nail & KC Remon. tag E. side 14" Apple N40°W 72.38'
- SW corner MBT Box N65°E 67.67'

On C/L East & West bit. road (Alpine Church)  
C/L North & South bit. road is 2' East



Signed by Kirk Breitels  
Surveyor's Michigan License No. 30077

Date 6/22/95