

**SURVEY & REMONUMENTATION**

APR 28 1995

KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

94 DEC 27 AM 9:04

For corners in  
KENT COUNTY  
(County)

Located In: Corner Code #

- |                                    |                   |       |
|------------------------------------|-------------------|-------|
| 1. Public Land Survey              | T 8N R 12W        | I-12  |
|                                    | T ___ R ___       | _____ |
|                                    | T ___ R ___       | _____ |
|                                    | T ___ R ___       | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
|                                    | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec.  | S ___ T ___ R ___ | _____ |
|                                    | S ___ T ___ R ___ | _____ |

*W. R. Byl*  
REG. OF DEEDS

7902

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, William R. Byl, in a field survey on Aug. 1, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- |                    |           |                          |
|--------------------|-----------|--------------------------|
| I-12 1837 GLO      | Whitcomb  | Set Post                 |
| 1972 Kent Co. Wit. |           | Conc. Monument           |
| 1981 LCRC #290     | VanKooten | Conc. Monument           |
| 1981 LCRC #2391    | Bueche    | Set Kent County Monument |
| 1990 LCRC #5398    | Starr     | Kent County Monument     |

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 12/22/94  
CHAIRMAN *Harry Huber*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 11/21/81 and was recorded per LCRC #2391

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-12 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the Angle Iron, "T" Iron and Conc. Monument he found. Said Irons & Conc. Monument check with Kent Co. Wit. and LCRC #290.

- |                                   |  |
|-----------------------------------|--|
| <u>LCRC #2391</u>                 | <u>LCRC #5398</u>                            |
| Nail & tag 12" Apple S40°E 84.03' | Nail & KC tag S. side P. Pole S70°W 74.50'   |
| Nail & tag P. Pole S70°W 74.50'   | "X" cut on E. end conc. culv. S57°E 25.45'   |
| "X" cut E. end culv. S57°E 25.40' | "X" cut on W. end conc. culv. S50°W 22.60'   |
| "X" cut W. end culv. S50°W 22.55' | SW cor. brick house N43°E 162.50'            |
| SW cor. brick hse. N43°E 162.47'  | Nail & KC tag N. side 8" Elm S60°E 39.25'    |
| C/L blktp. N-S is East 3' m/l     | C/L N-S bit. rd. is 4' E.; On C/L ditch West |
| Field division E & W              | On fence line East                           |

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-12 Standard Kent County Monument
- |  |       |         |
|--|-------|---------|
| Nail & KC Remon. tag S. side P. Pole         | S70°W | 74.50'  |
| "X" cut on E. end conc. culv.                | S57°E | 25.55'  |
| "X" cut on W. end conc. culv.                | S50°W | 22.30'  |
| SW cor. brick house                          | N43°E | 162.50' |
| New Nail & KC Remon. tag N. side 8" Elm      | S60°E | 39.28'  |
| C/L N-S bit. rd. is 4' E.; On C/L ditch West |       |         |
| On fence line East                           |       |         |



Signed by *W. R. Byl*  
Surveyor's Michigan License No. 23502

Date 12/07/94