

SEP 18 1995

KENT COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in KENT COUNTY (County)

Located In:

Corner Code #

- 1. Public Land Survey T 8N R 12W J-6
2. Property Controlling in Section S T R
3. Miscellaneous Property in Section S T R

Register of Deeds Stamp & File Number. Includes date 95 AUG 29 AM 10:39 and signature of Lucille Bond.

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 1-13. Cell J14 is circled.

I, Kirk Breitels, in a field survey on July 5, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Table with columns for date (J-6 1838, 1988, 1991), monument type (GLO, LCRC #4557, LCRC #6180), location (W. Glaza), and status (Not Set, Set Capped Rerod at Int. 1/4 lines, Set Kent County Monument).

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Wallace E. Glaza on 4/12/91 and was recorded per LCRC #6180.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-6 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Wallace E. Glaza in place of the Capped Rerod he found. Said Capped Rerod checks with LCRC # 4557.

- LCRC #4557
Nail & KC Remon. tag E. side 7" Maple N26°E 6.35'
Nail & KC Remon. tag S. side 16" Oak N76°E 40.37'
Nail & KC Remon. tag S. side 7" Poplar N67°W 11.16'
Nail & KC Remon. tag SW side 22" Oak N38°W 74.12'
Nail & KC Remon. tag W. side 14" oak N06°E 84.15'
North edge of field is South 7' ±

P.A. 345 1990 KENT COUNTY PEER APPROVED 8/24/95 CHAIRMAN [Signature]

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- J-6 Standard Kent County Monument
New Nail & KC Remon. tag E. side 9" Maple N26°E 6.40'
New Nail & KC Remon. tag S. side 18" Oak N76°E 40.39'
New Nail & KC Remon. tag S. side 10" Poplar N67°W 11.12'
New Nail & KC Remon. tag SW side 24" Oak N38°W 74.17'
New Nail & KC Remon. tag W. side 16" oak N06°E 84.17'
North edge of field is South 7' ±



Signed by [Signature]

Date 8/24/95

Surveyor's Michigan License No. 30077