

REMONUMENTATION

\$7.00 SEP 13 1995  
\$2.00 COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
KENT COUNTY  
(County)

Located In: Corner Code #

1. Public Land Survey T .8N R .12W -K-1

2. Property Controlling S T R  
in Section S T R

3. Miscellaneous S T R  
Property in Sec. S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

95 JUN 29 AM 11:56

REG. OF DEEDS  
8494

Register of Deeds Stamp & File Number

I, Kirk Breitals, in a field survey on Jan. 25, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- K-1 1838 GLO Whitcomb Set Post
- 1944 Kent Co. Wit. Leaded Stone
- 1980 LCRC #1378 Hackbardt Mon. Box
- 1983 LCRC #3210 McCloskey Mon. Box
- 1984 LCRC #4091 Kolehouse Set Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Randy. J. Kolehouse on 11/24/84 and was recorded per LCRC #4091.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-1 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Randy J. Kolehouse on the township line in place of the 3/4" Iron in a mon. box he found. Said Iron in a mon. box checks with Kent Co. Wit. and LCRC #1378 & #3210.

- LCRC #4091
- Nail & KC Remon. tag NE side G. Pole S45°E 38.97'
  - Nail & KC Remon. tag NW side P. Pole S60°W 76.02'
  - Nail & KC Remon. tag SW side P. Pole N60°W 75.07'
  - C/L manhole cover S75°W 17.9'
  - C/L 10 Mile Rd. (blktp.) running E-W is 1' m/l North
  - C/L Alpine Ave. (blktp.) running N-S is 17' m/l West
  - KC Mon. at SE cor. Sec. 35, T9N, R12W West 32.52'

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 6/22/95  
CHAIRMAN Harry Hubert

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-1 Standard Kent County Monument
- Set Nail & KC Remon. tag NE side Guy Pole (new) S45°E 38.88'
  - Nail & KC Remon. tag NW side P. Pole S60°W 76.02'
  - Nail & KC Remon. tag SW side P. Pole N60°W 75.04'
  - C/L manhole cover S75°W 17.90'
  - KC Mon. at SE cor. Sec. 35, T9N, R12W S90°W 32.52'
  - C/L 10 Mile Rd. (blktp.) running E-W is 1' m/l North
  - C/L Alpine Ave. (blktp.) running N-S is 17' m/l West



Signed by Kirk Breitals Date 3/20/95

Surveyor's Michigan License No. 30077