

SEP 18 1995

KENT COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in KENT COUNTY (County)

Located In:

Corner Code #

- 1. Public Land Survey T 8N R 12W K-8
2. Property Controlling in Section S T R
3. Miscellaneous Property in Section S T R

Register of Deeds Stamp & File Number. Includes date 95 AUG 29 AM 10:39 and State of Michigan County of Kent stamp.

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. Cell (8,24) is shaded.

I, Kirk Breitels, in a field survey on Aug. 1, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Table listing monuments: K-8 1838 GLO Whitcomb Set Post 1" Iron; 1972 LCRC #225 Spicer 1/2" Iron; 1981 LCRC #2393 Bueche Set Kent County Monument; 1990 LCRC #5412 Starr Kent County Monument.

P.A. 345 1990 KENT COUNTY PEER APPROVED 8/24/95 CHAIRMAN Harry Hubers

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 12/2/81 and was recorded per LCRC #2393.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-8 Found Capped Re-rod (#29245) at same position as standard Kent Co. Mon. (Harrison) per previous measurements and witnesses from above LCRC as set in 1981 by John C. Bueche in place of the 3/4" Re-rod and "T" Iron he found. Both Irons check with Kent Co. Wit. and LCRC #225. Set standard Kent Co. Mon. (Harrison) in place of the Capped Re-rod. LCRC #2393 & #5412

Table of corner evidence: 'X' cut on N. end conc. culv. N40°E 1.52'; 'X' cut on S. end conc. culv. S00°E 22.39' C/L joint to N. bound; SE cor. conc headwall N00°E 76.88' M-37 is West 37.12'; Nail & KC Remon. tag N. side 14" Box Elder S60°E 133.54'; Nail & KC Remon. tag N. side P. Pole N85°E 40.84'; C/L top Fire Hydrant N60°E 15.71'; C/L grav. dr. to hse. #5598 is S. 10' m/l; On tree row W.

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Table listing monument details: K-8 Standard Kent County Monument; Nail & KC Remon. tag N. side P. Pole N85°E 40.84'; C/L top Fire Hydrant N60°E 15.71'; SW cor. 1' x 1' conc. pad for light N40°E 59.89'; Cut 'X' on S. end conc. culv. N00°E 48.94'; Set Nail & KC Remon. tag W. side Light Pole S20°E 110.41'; On tree row West more or less; C/L joint N. bound M-37 is West 37.12' more or less.



Signed by Kirk Breitels

Date 8/24/95

Surveyor's Michigan License No. 30077