

SURVEY & REMONUMENTATION

APR 28 1995

KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

94 DEC 27 AM 9:04

For corners in
KENT COUNTY

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>12W</u>	K-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

W. R. Byl
REG. OF DEEDS

7908

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William R. Byl, in a field survey on July 19, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-13	1837	GLO	Brookfield	Set Post
	1975	LCRC #790	Hooth	1/2" Iron in Mon. Box
	1982	LCRC #3156	Hackbardt	Set Kent County Monument
	1990	LCRC #5417	Starr	Kent County Monument
	1992	LCRC #6638	McCloskey	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Glen S. Hackbardt on 8/4/82 and was recorded per LCRC #3156

P.A. 345 1990 KENT COUNTY
PEER APPROVED 12/22/94
CHAIRMAN *Harrison*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-13 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Glen S. Hackbardt in place of the 1/2" Iron he found inside a mon. box. Said Iron in mon. box checks with LCRC #790.

LCRC #3156		LCRC #5417 & 6638	
C/L Hydrant	S10°W 69.95'	C/L Hydrant	S10°W 69.95'
C/L MBT Manhole	S45°W 45.92'	C/L Water Manhole	S45°W 45.92'
C/L W. Manhole	S45°W 45.92'	C/L Sanitary Manhole	N60°W 82.40'
C/L S. Manhole	N60°W 82.40'	C/L Manhole	North 83.40'
C/L Manhole	North 83.40'	Nail & KC Remon. tag E. side P. Pole	S30°W 37.73'
Nail & tag CP	N20°W 55.55'	Nail & KC Remon. tag W. side P. Pole	N20°W 65.65'
		KC Mon. - K-1	East 75.87'
		PK Nail @ C/L 4 Mile & Alpine	East 40.42'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13 Standard Kent County Monument			
C/L Hydrant	S10°W	69.95'	
C/L Water Manhole	S45°W	45.88'	
C/L Sanitary Manhole	N60°W	82.36'	
C/L Manhole	North	83.38'	
Nail & KC Remon. tag E. side P. Pole	S30°W	37.73'	
Nail & KC Remon. tag W. side P. Pole	N20°W	65.60'	
Kent Co. Mon. (K-1, T7N, R12W)	N90°E	75.92'	
PK Nail @ C/L 4 Mile & Alpine	N90°E	40.42'	



Signed by *W. R. Byl*
Surveyor's Michigan License No. 23502

Date 12/07/94