

\$7.00  
\$2.00

SEP 18 1993

### KENT COUNTY REMONUMENTATION

#### LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
KENT COUNTY  
(County)

Located In:

Corner Code #

- |                                      |   |           |   |            |            |
|--------------------------------------|---|-----------|---|------------|------------|
| 1. Public Land Survey                | T | <u>8N</u> | R | <u>12W</u> | <u>L-1</u> |
|                                      | T | _____     | R | _____      | _____      |
|                                      | T | _____     | R | _____      | _____      |
|                                      | T | _____     | R | _____      | _____      |
| 2. Property Controlling in Section   | S | _____     | T | _____      | R          |
|                                      | S | _____     | T | _____      | R          |
| 3. Miscellaneous Property in Section | S | _____     | T | _____      | R          |
|                                      | S | _____     | T | _____      | R          |

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
95 JUN 29 AM 11:57  
REG. OF DEEDS  
*[Signature]*  
8503

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kirk Breitels, in a field survey on Jan. 25, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-1	1838	GLO	Whitcomb	Not Set
	1954	Kent Co. Wit.		Iron
	1971	LCRC #74	Chambers	1" Iron
	1983	LCRC #3210	McCloskey	Mon. Box
	1984	LCRC #4092	Kolehouse	Set Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Randy J. Kolehouse on 11/24/84 and was recorded per LCRC #4092

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-1 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Randy j. Kolehouse on the township line in place of the 3/4" Iron he found inside a mon. box. Said Iron checks with Kent Co. Wit. and LCRC's #74 & #3210.

LCRC #4092

Nail & KC Remon. tag NW side P. Pole	N35°E	48.25'
Nail & KC Remon. tag NE side Elec. Serv. Pole	S45°E	37.94'
Nail & KC Remon. tag NW side P. & TV Pole	S40°W	38.28'
SE cor. hse. fnd. (old church)	N40°W	74.22'
NE cor. frame hse.	S36°W	100.65'
Chiseled "X" on N. end 12" conc. culv.	N50°E	46.30'
KC Mon. at S 1/4 cor. Sec. 36, T9N, R12W	West	16.26'


P.A. 345 1990 KENT COUNTY  
PEER APPROVED 6/22/99  
CHAIRMAN *[Signature]*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-1 Standard Kent County Monument

Nail & KC Remon. tag NW side P. Pole	N35°E	48.27'
Nail & KC Remon. tag NE side Elec. Serv. Pole	S45°E	37.96'
Nail & KC Remon. tag NW side P. & TV Pole	S40°W	38.28'
SE cor. hse. fnd. (old church)	N40°W	74.22'
NE cor. frame hse.	S36°W	100.65'
Chiseled "X" on N. end 12" conc. culv.	N50°E	46.28'
KC Mon. at S 1/4 cor. Sec. 36, T9N, R12W	S90°W	16.20'



Signed by *[Signature]*

Date 3/20/95

Surveyor's Michigan License No. 30077