

RECORDED
 \$7.00
 \$2.00
 SEP 18 1995

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
 (County)

Located In:

Corner Code #

1. Public Land Survey	T	8N	R	12W	L-5
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T		R
	S		T		R
3. Miscellaneous Property in Section	S		T		R
	S		T		R

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 95 JUN 29 AM 11:57
 REG. OF DEEDS
Lucy J. Jones

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	6	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kirk Breitels, in a field survey on Feb. 24, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-5	1838	GLO	Whitcomb	Set Post
		Kent Co. Wit.		1" Iron
	1974	LCRC #738	Bonnema	"T" Iron
	1981	LCRC #2615	Nederveld	Set Kent County Monument
	1990	LCRC #5419	Starr	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Gordon D. Nederveld on 9/15/81 and was recorded per LCRC #2615

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-5 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Gordon D. Nederveld in place of the "T" Iron over a 1" Iron he found. Both Irons check with Kent Co. Wit. and LCRC #738.

LCRC #2615 & #5419

Nail & KC Remon. tag NW side P. Pole	S38°W	73.91'	P.A. 345 1990 KENT COUNTY
Nail & KC Remon. tag E. side P. Pole	N08°W	135.40'	PEER APPROVED 6/22/95
Nail & KC Remon. tag N. side 30" W. Cherry	S82°E	164.20'	CHAIRMAN <i>Harry Hubert</i>
NE cor. house foundation	S52°W	135.44'	
Top center Tele. Box	N60°E	28.70'	
Top center Tele. Box	N55°W	54.86'	

On C/L blacktop road - West; C/L of N-S blacktop road - 6.5' West

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-5 Standard Kent County Monument

Nail & KC Remon. tag NW side P. Pole	S38°W	73.93'	
Set Nail & KC Remon. tag E. side P. Pole	N08°W	135.44'	(new pole)
New Nail & KC Remon. tag N. side 34" W. Cherry	S82°E	164.03'	
NE cor. house foundation	S52°W	135.44'	
Top center Tele. Box	N60°E	28.70'	
Top center Tele. Box	N55°W	54.89'	

On C/L blacktop road - West; C/L of N-S blacktop road - 6.5' West



Signed by *Kirk Breitels*
 Surveyor's Michigan License No. 30077

Date 6/22/95