

**SURVEY & REMONUMENTATION**

APR 28 1995

KENT COUNTY REMONUMENTATION

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
94 DEC 27 AM 9:04

For corners in  
**KENT COUNTY**  
(County)

Located In: Corner Code #

1. Public Land Survey	T <u>8N</u> R <u>12W</u>	L-11
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*W. R. Byl*  
REG. OF DEEDS

7909

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William R. Byl, in a field survey on Aug. 1, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

L-11	1838	GLO	Whitcomb	Set Post
	1960	Kent Co. Wit.	Bonnema	"X" in pavement
	1977	LCRC #1057	Nederveld	3/4" Iron in mon. box
	1981	LCRC #2614	Starr	Set Kent County Monument
	1990	LCRC #5422		Kent County Monument

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 12/22/94  
CHAIRMAN Stan Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Gordon D. Nederveld on 9/15/81 and was recorded per LCRC #2614

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-11 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Gordon D. Nederveld in place of the 3/4" Iron he found inside a mon. box. Said Iron in mon. box checks with Kent Co. Wit. and LCRC #1057.

LCRC #2614		LCRC #5422	
Nail & tag P. Pole	S00°W 29.65'	Nail & KC tag W. side P. Pole	S00°W 29.65'
Nail & tag Tw. Maple	N00°E 35.80'	NE cor. porch foundation	S21°W 88.80'
NE cor. porch fnd.	S21°W 88.80'	NW cor. hse. foundation	S39°E 124.50'
NW cor. hse. fnd.	S39°E 124.50'	Plat Mon.	N00°E 50.01'
Plat Mon.	N00°E 50.01'	Nail & KC tag W. side 12" Maple	N30°W 50.35'
		Nail & KC tag SE side 10" Tree	N60°E 87.58'
		On C/L E-W bit. rd.; On fence line N.	
		On tree row N-S	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-11 Standard Kent County Monument			
Nail & KC Remon. tag W. side P. Pole	S00°W	29.65'	
NE cor. porch foundation	S21°W	88.85'	
NW cor. hse. foundation	S39°E	124.53'	
Plat Monument	N00°E	50.01'	
New Nail & KC Remon. tag W. side 12" Maple	N30°W	50.37'	
New Nail & KC Remon. tag SE side 10" Tree	N60°E	87.62'	
On C/L E-W bit. rd.; On fence line N.			
On tree row N-S			



Signed by *W. R. Byl*  
Surveyor's Michigan License No. 23502

Date 12/07/94