

\$7.00  
\$2.00

SEP 19 1995

### KENT COUNTY REMONUMENTATION

### LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
KENT COUNTY  
(County)

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey	T	<u>8N</u>	R	<u>12W</u>	<u>M-3</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

95 JUN 29 PM 12: 00

REG. OF DEEDS  
*Luci Standa*  
8510

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Feb. 6, 19 95

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE:** Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K
2	6	5	4	3	2					
3										
4	7	8	9	10	11	1				
5										
6	18	17	16	15	14	1				
7										
8	19	20	21	22	23	2				
9										
10	30	29	28	27	26	2				
11										
12	31	32	33	34	35	3				
13										

**A. Description of original monument and accessories and/or subsequent restoration:**

M-3	1837	GLO	Brookfield	Set Post
		Kent Co. Wit.		Conc. Mon.
	1972	LCRC #224	Spicer	Conc. Mon.
	1974	LCRC #762	Bonnema	Conc. Mon.
	1981	LCRC #2139	Jonker	Set Kent County Monument
	1990	LCRC #5425	Starr	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 8/24/81 and was recorded per LCRC #2139.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

M-3 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the Conc. Mon. he found. Said Conc. Mon. checks with Kent Co. Wit. and LCRC's #224 & #762.

LCRC #2139 & #5425

Nail & KC Remon. tag S. side 30" Tw. Willow	S53°E	110.30'
Nail & KC Remon. tag E. side 15" Elm	S25°W	35.25'
Top C/L Tel. Box	N00°W	81.33'
On Division Ave. - North - extended South		
On C/L 9 Mile East - extended West		

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 6/22/95  
CHAIRMAN *[Signature]*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

M-3 Standard Kent County Monument

New Nail & KC Remon. tag S. side 36" Tw. Willow	S53°E	110.28'
Top C/L Tel. Box	N00°W	81.33'
Set Nail & KC Remon. tag W. side 18" Ash	S30°W	19.77'
Set Nail & KC Remon. tag N. side 4" Ash	N65°W	8.62'
C/L top W'ly end 12" CMP	N60°E	85.6'
On Division Ave. - North - extended South		
On C/L 9 Mile East - extended West		



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 6/22/95