

\$7.00
\$2.00
SEP 18 1995
COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located In:

Corner Code #

1. Public Land Survey	T	8N	R	12W	M-4
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
95 JUN 29 PM 12:00
REG. OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K
2	6	5	4	3					2	
3										
4	7	8	9	10	11					
5										
6	18	17	16	15	14					
7										
8	19	20	21	22	23					
9										
10	30	29	28	27	26					
11										
12	31	32	33	34	35					
13										

I, Kirk Breitels, in a field survey on Feb. 6, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-4	1837	GLO	Brookfield	Set Post
		Kent Co. Wit.		Conc. Mon.
	1973	LCRC #523	Spicer	Conc. Mon.
	1981	LCRC #2137	Jonker	Set Kent County Monument
	1990	LCRC #5426	Starr	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 8/24/81 and was recorded per LCRC #2137.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-4 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the Conc. Mon. he found. Said Conc. Mon. checks with Kent Co. Wit. and LCRC #523.

LCRC #2137 & #5426

Nail & KC Remon. tag SE side 12" Ash	N40°E	10.80'	P.A. 345 1990 KENT COUNTY
Nail & KC Remon. tag NE side 9" Ash	S30°E	9.95'	PEER APPROVED 6/22/95
Nail & KC Remon. tag NW side Tw. 8" Ash	S60°W	7.83'	CHAIRMAN <i>[Signature]</i>
Nail & KC Remon. tag N. side 6" Ash	N89°E	20.53'	
On tree line N-S			
On field line West			

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-4 Standard Kent County Monument

Nail & KC Remon. tag SE side 12" stump	N40°E	10.93'
New Nail & KC Remon. tag NE side 15" Ash	S30°E	9.95'
New Nail & KC Remon. tag NW side Tw. 12" Ash	S60°W	7.63'
Nail & KC Remon. tag N. side 6" Ash	N89°E	20.58'
On tree line N-S		
On field line West		



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 6/22/95