

SURVEY & REMONUMENTATION

SEP 18 1995

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in KENT COUNTY (County)

Located In:

Corner Code #

1. Public Land Survey	T	8N	R	12W	M-6
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

95 AUG 29 AM 10:39

REG. OF DEEDS
8701

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		0		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Kirk Breiteis, in a field survey on March 1, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-6	1837	GLO	Brookfield	Set Post
	1954	Kent Co. Wit.		Stone & Iron
	1977	LCRC #1039	Bonnema	1/2" Soild Iron
	1981	LCRC #2138	Jonker	Set Kent County Monument
	1990	LCRC #5428	Starr	Kent County Monument

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 8/24/95
 CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 8/24/81 and was recorded per LCRC #2138.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-6 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the 1/4" x 8" Spike over a 1/2" Round Iron he found. Both Spike and Iron check with Kent Co. Wit. and LCRC #1039.
LCRC #2138 & #5428

Nail & KC Remon. tag NW side T. & P. Pole	S57°W	75.36'
Nail & KC Remon. tag SW side 14" Maple	N65°W	81.76'
Nail & KC Remon. tag NW side T. Pole	N18°E	119.04'
Nail & KC Remon. tag E. side 26" Walnut	N20°W	83.55'
Nail & KC Remon. tag W. side 30" Maple	S20°E	66.75'

On C/L blacktop road - West - South - North
 C/L blacktop road - East is 2' South

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-6 Standard Kent County Monument

Nail & KC Remon. tag NW side T. & P. Pole	S57°W	75.39'
Nail & KC Remon. tag SW side 18" Maple	N65°W	81.84'
Nail & KC Remon. tag W. side T. Pole	N18°E	119.74'
Nail & KC Remon. tag E. side 30" Walnut	N20°W	83.59'
Nail & KC Remon. tag W. side 33" Maple	S20°E	66.75'

On C/L blacktop road - West - South - North
 C/L blacktop road - East is 2' South



Signed by [Signature]

Date 8/24/95

Surveyor's Michigan License No. 30077