

\$7.00
\$2.00

SEP 1 8 1995

COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located In:

Corner Code #

1. Public Land Survey	T	<u>8N</u>	R	<u>12W</u>	<u>M-7</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T		
	S		T		
3. Miscellaneous Property in Section	S		T		
	S		T		

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

95 JUN 29 PM 12:08
51

REG. OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1
3											
4	7		8		9		10		11		12
5											
6	18		17		16		15		14		13
7											
8	19		20		21		22		23		24
9											
10	30		29		28		27		26		25
11											
12	31		32		33		34		35		36
13											

I, Kirk Breitels, in a field survey on Feb. 20, 1995,

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-7	1837	GLO	Brookfield	Set Post
	1959	Kent Co. Wit.		Conc. Mon.
	1973	LCRC #591	Bonnema	3/4" Iron
	1983	LCRC #3214	Stadt	Set Kent County Monument
	1990	LCRC #5429	Starr	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Russel E. Stadt on 3/7/83 and was recorded per LCRC #3214.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-7 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Russell E. Stadt in place of the 3/4" Iron he found inside a mon. box. Said Iron checks with Kent Co. Wit. and LCRC #591.

LCRC #3214 & 5429

Nail & KC Remon. tag SE side T. Pole	N40°E	42.95'	P.A. 345 1990 KENT COUNTY
Nail & KC Remon. tag SW side T. Pole	N45°W	46.19'	PEER APPROVED 6/22/95
Nail & KC Remon. tag W. side P. & T. Pole	S30°E	65.81'	CHAIRMAN <i>[Signature]</i>
Nail & KC Remon. tag N. side cor. wood fence post	S75°W	97.88'	

Monument is at C/L "X" of Division Ave. & 7 Mile Rd.

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-7 Standard Kent County Monument

Nail & KC Remon. tag SE side T. Pole	N40°E	42.98'
Nail & KC Remon. tag SW side T. Pole	N45°W	46.21'
Nail & KC Remon. tag W. side P. & T. Pole	S30°E	65.85'
Set Nail & KC Remon. tag N. side fence post	S80°W	127.32'

Monument is at C/L "X" of Division Ave. & 7 Mile Rd.



Signed by Kirk Breitels

Date 6/22/95

Surveyor's Michigan License No. 30077