

\$7.00  
\$2.00

SEP 18 1995

KENT COUNTY REMONUMENTATION

COMMISSIONER

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
KENT COUNTY  
(County)

Located In:

Corner Code #

1. Public Land Survey	T	<u>8N</u>	R	<u>12W</u>	<u>M-8</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
95 JUN 29 PM 12: 00  
REG. OF DEEDS  
*Lucy Stone*  
8514

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K
2	6	5	4	3	2					
3										
4	7	8	9	10	11					
5										
6	18	17	16	15	14					
7										
8	19	20	21	22	23					
9										
10	30	29	28	27	26					
11										
12	31	32	33	34	35					
13										

I, Kirk Breitels, in a field survey on May 10, 19 95

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-8	1837	GLO	Brookfield	Set Post
		Kent Co. Wit.		Boat Spike
	1973	LCRC #591	Bonnema	Boat Spike
	1974	LCRC #734	Spicer	Boat Spike
	1981	LCRC #2140	Jonker	Set Kent County Monument
	1990	LCRC #5430	Starr	Kent County Monument
	1993	LCRC #6781	Brintnall	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 8/24/81 and was recorded per LCRC #2140.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-8 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the Boat Spike over a stone he found. Said Boat Spike and Stone check with Kent Co. Wit. and LCRC's #591 & #734.  
LCRC #2140 & 5430 & 6781

SE corner of chain link fence post	N40°W	66.69'
NW corner of conc slab for large rock	N50°E	66.75'
Nail & KC Remon. tag N. side P. Pole	S85°E	34.37'
NW corner brick garage	S65°E	118.07'
Nail & KC Remon. tag W. side P. Pole	S12°E	74.32'
NE cor. garage siding house #5595	S75°W	84.06'
Nail & KC Remon. tag N. side P. Pole	N90°W	48.38'

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 6/22/95  
CHAIRMAN *Harry Huber*

C/L bit. rd. 3.3' West; On fence line to West

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-8 Standard Kent County Monument

SE corner of chain link fence post	N40°W	66.73'
NW corner of conc slab for large rock	N50°E	66.75'
Nail & KC Remon. tag N. side P. Pole	S85°E	34.37'
NW corner brick garage	S65°E	118.16'
Nail & KC Remon. tag W. side T. Pole	S12°E	74.28'
NE cor. garage siding house #5595	S75°W	84.06'
Nail & KC Remon. tag N. side P. Pole	N90°W	48.38'

C/L bit. rd. 3.3' West; On fence line to West



Signed by Kirk Breitels Date 6/22/95  
Surveyor's Michigan License No. 30077