

SEP 18 1995

KENT COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in KENT COUNTY (County)

Located In:

Corner Code #

1. Public Land Survey	T	8N	R	12W	M-10
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S	T	R		
	S	T	R		
3. Miscellaneous Property in Section	S	T	R		
	S	T	R		

REG. OF DEEDS

8702

95 AUG 29 AM 10:39

STATE OF MICHIGAN COUNTY OF KENT RECEIVED FOR RECORD

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kirk Breitels, in a field survey on Aug 1, 1995

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-10	1838	GLO	Brookfield	Set Post
	1935	Kent Co. Wit.		1" Iron
	1971	LCRC #72	Chambers	1" Iron
	1984	LCRC #3839	Kolehouse	Set Kent County Monument
	1990	LCRC #5432	Starr	Kent County

P.A. 345 1990 KENT COUNTY

PEER APPROVED 8/24/95  
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Randy J. Kolehouse on 4/21/84 and was recorded per LCRC #3839

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-10 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Randy J. Kolehouse in place of the 1" Iron he found. Said 1" Iron checks with Kent Co. Wit. and LCRC #72.

LCRC #3839 & #5432

Nail & KC Remon. tag SE side	15" Oak	S35°W	50.05'
Nail & KC Remon. tag S. side	8" Pine	S85°E	44.30'
Nail & KC Remon. tag NW side	10" Oak	N45°E	53.48'
Iron in top of stone pillar		N40°W	48.52'
SE corner of stone pillar		West	29.78'

On fence line to West; C/L N-S bit. road is 3' E.

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-10 Standard Kent County Monument

New Nail & KC Remon. tag SE side	24" Oak	S35°W	50.05'
New Nail & KC Remon. tag S. side	12" Pine	S85°E	44.32'
Nail & KC Remon. tag NW side	12" Oak	N45°E	53.48'
Iron in top of stone pillar		N40°W	48.48'
SE corner of stone pillar		West	29.68'

On fence line to West; C/L N-S bit. road is 3' E.



Signed by [Signature]

Date 8/24/95

Surveyor's Michigan License No. 30077