

SURVEY & REMONUMENTATION

APR 28 1995

KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

94 DEC 27 AM 9:05

For corners in
KENT COUNTY

W. R. Byl
REG. OF DEEDS

(County)	Located In:	Corner Code #
1. Public Land Survey	T 8N R 12W	M-11
	T R also	
	T 8N R 11W	A-11
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

7911
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William R. Byl, in a field survey on Aug. 1, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-11	1837	GLO	Brookfield	Set Post
		Kent Co. Wit.		Iron at fence post
	1977	LCRC #1057		1 1/4" Iron
	1981	LCRC #2135		Set Kent County Monument
	1990	LCRC #5433	Starr	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 8/24/81 and was recorded per LCRC #2135

P.A. 345 1990 KENT COUNTY
PEER APPROVED 12/22/94
CHAIRMAN *Robert J. Jonker*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-11 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the 1 1/4" x 36" Iron Pipe he found. Said Iron Pipe checks with Kent Co. Wit. and LCRC #1057.

<u>LCRC #2135</u>	<u>LCRC #5433</u>
Iron N. 12.04'	
Remon. tag 20" Beech	N01°W 29.17' same witnesses as LCRC #2135
Remon. tag 30" Tw. Oak	S89°E 47.95'
Remon. tag 30" Oak	S35°E 37.72'
Remon. tag 20" W. Cherry	N25°W 12.97'
On N-S fence	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-11 Standard Kent County Monument	
Iron	N00°E 12.04'
New Nail & KC Remon. tag W. side 24" Beech	N01°W 29.18'
New Nail & KC Remon. tag N. side 36" Tw. Oak	S89°E 47.89'
New Nail & KC Remon. tag SW side 36" Oak	S35°E 37.78'
Nail & KC Remon. tag SW side 24" W. Cherry	N25°W 12.97'
On N-S fence	



Signed by *W. R. Byl*
Surveyor's Michigan License No. 23502

Date 12/07/94