

**SURVEY & REMONUMENTATION**

APR 28 1995

KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

94 DEC 27 AM 9:05

For corners in  
KENT COUNTY

(County)	Located In:	Corner Code #
1. Public Land Survey	T. 8N R. 12W	M-12
	T. R. also	
	T. 8N R. 11W	A-12
	T. R.	
2. Property Controlling in Section	S. T. R.	
	S. T. R.	
3. Miscellaneous Property in Sec.	S. T. R.	
	S. T. R.	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

*W. R. Byl*  
REG. OF DEEDS

7912

Register of Deeds Stamp & File Number

I, William R. Byl, in a field survey on Oct. 20, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	6	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

M-12	1837	GLO	Brookfield	Set Post
		Kent Co. Wit.		Sq. Conc. Mon. with brass plate
	1979	LCRC #1334	Byl	Sq. Conc. Mon.
	1984	LCRC #3742	Chettleburgh	6 1/2" Sq. Conc. Mon.
	1985	LCRC #4156	Chettleburgh	Set Kent County Monument
	1990	LCRC #5434	Starr	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Thom. M. Chettleburgh on 4/3/85 and recorded per LCRC #4156.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-12 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Thomas M. Chettleburgh in place of the 6 1/2" square Conc. Mon. he found. Said square Conc. Mon. checks with Kent Co. Wit. and LCRC's #1334 & #3742.

LCRC #4156 & 5434

Nail & KC Remon. tag NW side 29" Willow	N41°E	152.44'
Nail & KC Remon. tag SW side Light Pole	S50°E	175.68'
Nail & KC Remon. tag E. side 27" Maple	S13°E	275.12'
Nail & KC Remon. tag NW side 12" Beech	S53°W	161.85'
Nail & KC Remon. tag W. side 29" Maple	N08°W	236.24'
Chain link fence East 2'; C/L bit. dr. to main. bldg. is S. 98'		
In Dwight Lydell Park - Between fish ponds		

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-12 Standard Kent County Monument

New Nail & KC Remon. tag NW side 36" Willow	N41°E	151.98'
Nail & KC Remon. tag SW side Light Pole	S50°E	175.73'
New Nail & KC Remon. tag E. side 30" Maple	S13°E	275.17'
New Nail & KC Remon. tag NW side 18" Beech	S53°W	161.79'
New Nail & KC Remon. tag W. side 33" Maple	N08°W	236.33'
Chain link fence East 2'; C/L bit. dr. to main. bldg. is South 98'		
In Dwight Lydell Park - Between fish ponds		



Signed by *W. R. Byl*  
Surveyor's Michigan License No. 23502

Date 12/07/94