

**SURVEY &
REMONUMENTATION**

MAY 22 2000

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION**

For corners in

<u>Kent</u> (County)	Located in: <u>Oakfield</u> Township	Corner Code # <u>A-10</u>
1. Public Land Survey	T <u>9N</u> R <u>9W</u>	<u>A-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REG. OF DEEDS

[Signature]

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 OCT 15 AM 8:09

11399

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Randy Kolehouse, in a field survey on January 12 19 99, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-10	1837	G.L.O. Notes	Cathcart	Set Post
	1862	Notes	Consumers Power Co.	Set 1/2" Rerod and Cap
	1984	L.C.R.C. #3778	William R. Byl	Fnd. 1/2" Rerod w/ CP Cap / Set K.C. Monument
	1991	L.C.R.C. #6213	Chris Marschall	K.C. Monument

**P.A. 345 1990 KENT COUNTY
PEER APPROVED 7/29/99**

CHAIRMAN William Byl
[Signature]

Note: This corner is common with M-10, T9N, R10W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by William Byl on 3/19/84 and was recorded per L.C.R.C. #3778.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-10 Found a Standard Kent County Monument 1' West of the C/L of Ramsdell Drive (bit.) running North and South, on line of a fence line running West, per L.C.R.C.'s #3778 and #6213 as set by William Byl in place of a 1/2" re-rod and cap he found as set in 1972 by Consumers Power Company

L.C.R.C. #3778A

L.C.R.C. #6213

Nail & tag, S. sd. Power Pole N 90 E 301.30'

Chiseled "X" in top of 12" conc. culv. S. End N 64 W 23.51' (m. 23.50')
Chiseled "X" in top of 12" conc. culv. N. End N 41 W 32.70' (m. 32.73')
Nail & tag S. sd. P.P. N 90 E 301.29' (m. 301.32')
G & A capped iron #9548 West 32.98' (m. 32.94')

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-10 Standard Kent County Monument

- Chiseled "X" top 12" conc. culv. S end N 64° W 23.50'
- Chiseled "X" top 12" conc. culv. N end N 41° W 32.73'
- Nail & K.C. remon. tag on W side P. pole N 05° W 350.54'
- Nail & K.C. remon. tag on S side P. pole N 90° E 301.32'
- SE cor. metal bldg. N 18° W 326.19'
- G & A capped iron #9548 N 90° W 32.94'
- C/L of bit. road running N-S, East 1.0'
- On fence line running West



Signed by *[Signature]* Date 9-27-99
WILLIAMS & WORKS

Surveyor's Michigan License No. 25854