

**SURVEY &
REMONUMENTATION**

MAY 22 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

SECTION

<u>Kent</u> (County)	Located in: Oakfield Township	Corner Code #
1. Public Land Survey	T <u>9N</u> R <u>9W</u>	<u>A-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REG. OF DEEDS

[Signature]

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 OCT 15 AM 8:09

11400

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Randy Kolehouse, in a field survey on March 16 19 99, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-11	1837	G.L.O. Notes	Cathcart	Set Post
	1962	Witness Map	K.C. Surveyor	Monument Box / Boat Spike
	1978	L.C.R.C. #1205	Nederveld & Jonker	Round Iron in Monument Box (A-11, T9N, R9W)
	1982	L.C.R.C. #3120	Williams & Works	Fnd. 3/4" Iron in Mon. Box / Set K.C. Mon. (A-11, T9N, R9W)

Note: This corner is common with M-11, T9N, R10W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Williams & Works on 10/18/82 and was recorded per L.C.R.C. #3120.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-11 Found a Standard Kent County Monument on the C/L intersection of 11 Mile Road (bit.) running East and West, Ramsdell Drive (bit.) running North and South, on line of a fence line running South, per L.C.R.C.'s #1205 and #3120 as set by Williams & Works in place of a 3/4" iron they found in a monument box which checked the K.C. Surveyor's records.

L.C.R.C. #3120

PK Nail & KC Remon tag in Curb Joint N 30°E 37.75' (m. 37.71')
Nail & KC Remon tag in E side 6" Elm N 10°W 134.60' (m. 134.53')

P.A. 345 1990 KENT COUNTY
PEER APPROVED 7/29/99
CHAIRMAN [Signature]

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-11 Standard Kent County Monument

- Nail & K.C. remon. tag on W side 6" Oak S 05° E 111.52'
- Nail & K.C. remon. tag on N side 10" Oak S 80° W 233.67'
- Nail & K.C. remon. tag on S side 8" dia. fence post N 80° W 139.15'
- Nail & K.C. remon. tag on E side 12" Elm N 10° W 134.53'
- PK nail top curb joint N 30° E 37.71'
- On C/L "X" of bit. roads running N-S & E-W
- On fence line running S



Signed by Randy J. Kolehouse Date 9-27-99

WILLIAMS & WORKS

Surveyor's Michigan License No. 25854