

MAY 22 2000

\$7.00
\$2.00

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

Kent (County)	Located in: Oakfield Township	Corner Code #
1. Public Land Survey	T <u>9N</u> R <u>9W</u>	<u>A-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REG. OF DEEDS

1999 OCT 15 AM 8:09

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

11401

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Randy Kolehouse in a field survey on February 3 19 99, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-12	1837	G.L.O. Notes	Cathcart	Set Post
	N/A	Witness Map	K.C. Surveyor	Conc. Monument
	1974	L.C.R.C. #623	David L. South	3" Conc. Monument (M-12, T9N, R10W)
	1982	L.C.R.C. #3122	Williams & Works	3" Conc. Monument (M-12, T9N, R10W)
	1991	L.C.R.C. #6212	Chris Marshall	3" Conc. Monument (M-12, T9N, R10W)

Note: This corner is common with M-12, T9N, R10W.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-12 Found a 3" diameter concrete monument projecting 3" above a 24" concrete base 80' ± East of the West edge of a swamp, on line of a tree row running West, per L.C.R.C.'s #623, #3122, and #6212.

L.C.R.C. #3122

L.C.R.C. #6212

Nail & KC Remon tag in S side 4" Elm N 60°E 5.60'
 Nail & KC Remon tag in E side 12" Elm S 10°E 25.68'
 Nail & KC Remon tag in E side 8" Maple N 10°W 69.30'
 Nail & KC Remon tag in S side 8" Maple N 55°W 43.50'
 Nail & KC Remon tag in S side 12" Wild Cherry N 75°W 71.82'
 Steel fence post North 1.50'
 1" Iron 4'+/- South and 1.7'+/- East of corner

Nail & Tag E sd. 18" Elm S 10 E 25.69' (m. 25.67')
 Nail & Tag S sd. 14" Elm N 60 E 5.73' (m. 5.72')
 Nail & tag S sd. 10" Maple Clump N 55 W 43.25' (m. 42.24')
 Nail & tag N sd. 16" W. Cherry N 90 W 71.61' (m. 71.60')
 Nail & tag E sd. 10" Maple N 10 W 69.30' (m. 68.49')
 Steel FNC. Post North 1.50' (m. 1.55')
 Iron pipe 4' more or less south & 1.7' more or less East of corner
 Corner is on tree line to west extended east
 West edge of swamp is 80' more or less west

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


A-12 3" Diameter Concrete Monument

Nail & K.C. remon. tag on E side 18" Elm S 10° E 25.67'
 Nail & K.C. remon. tag on S side 14" Elm N 60° E 5.72'
 Nail & K.C. remon. tag on S side 12" Maple clump N 55° W 42.24'
 Nail & K.C. remon. tag on N side 20" W. Cherry N 90° W 68.49'
 Iron pipe 14' m/l S & 1.7' m/l E of corner
 On tree row running W

P.A. 345 1990 KENT COUNTY

PEER APPROVED 7/29/99

CHAIRMAN



Signed by Randy J. Kolehouse Date 9-27-99

WILLIAMS & WORKS

Surveyor's Michigan License No. 25854