

**SURVEY &  
REMONUMENTATION**

MAY 22 2000

**\$7.00  
\$2.00**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
KENT COUNTY REMONUMENTATION**

For corners in

Kent (County)	Located in:	Oakfield Township	Corner Code #
1. Public Land Survey	T <u>9N</u>	R <u>9W</u>	<u>B-1</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

REG. OF DEEDS

*[Signature]*

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
1999 DEC -8 AM 10:06

**11540**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Randy Kolehouse, in a field survey on August 12 19 99, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

B-1 This corner was not originally set by the G.L.O.

Year	Witness Map	K.C. Surveyor	Monument
1938	Witness Map	John Bueche	Monument
1984	L.C.R.C. #4004	John Bueche	Fnd. Conc. Monument / Set K.C. Monument
1992	L.C.R.C. #6426	John Bueche	K.C. Monument

Note: This corner is not common with B-13, T10N, R9W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by John Bueche on 10/12/84 and was recorded per L.C.R.C. #4004.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-1 Found a Standard Kent County Monument on the C/L of 16 Mile Road (gravel) running East and West 1.0' below grade per L.C.R.C.'s #4004 and #6426 as set by John Bueche in place of a concrete monument he found 1.5' below grade which checked the K.C. Surveyor's records.

L.C.R.C. #4004

L.C.R.C. #6426

K.C. Remon. tag & nail in W. side 12" dbl. Oak S 45° W 25.84'  
K.C. Remon. tag & nail in E. side 16" dbl. Oak S 10° E 19.76'  
K.C. Remon. tag & nail in N. side 14" Oak S 45° E 37.29'  
K.C. Remon. tag & nail in N. side 20" Oak S 65° E 73.43'  
K.C. Remon. tag & nail in W. face 26" Oak N 80° E 118.88'  
C/L gravel road E-W is South 6'+/-  
C/L 2 track South 30'+/- West

K.C. Remon. Tag & nail W side Quad 14" Oak S 45° W 25.84' (m. 25.82')  
K.C. Remon. Tag & Nail E side Dbl. 18" Oak S 10° E 19.76' (m. 19.75')  
K.C. Remon. Tag & Nail N side 16" Oak S 45° E 37.29' (m. 37.25')  
K.C. Remon. Tag & Nail N side 22" Oak S 65° E 73.43' (m. 73.46')  
K.C. Remon. Tag & Nail W side 30" Oak N 80° E 118.88' (m. 118.74')  
K.C. Mon. (S 1/4 31, 10-9) West 132.00'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-1 Standard Kent County Monument

Nail & K.C. remon. tag on W. side dbl. 14" Oak S 45° W 25.82'  
Nail & K.C. remon. tag on E side dbl. 18" Oak S 10° E 19.75'  
Nail & K.C. remon. tag on N side 16" Oak S 45° E 37.25'  
Nail & K.C. remon. tag on N side 22" Oak S 65° E 73.46'  
Nail & K.C. remon. tag on W side 30" Oak N 80° E 118.74'  
On C/L of gravel road running E-W  
K.C. Mon., B-13, T10N, R9W, East 132.00'

Signed by *Randy J. Kolehouse* Date \_\_\_\_\_

WILLIAMS & WORKS

Surveyor's Michigan License No. 25854

