

JAN 24 1996

KENT COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in KENT COUNTY (County)

Located In:

Corner Code #

1. Public Land Survey	T	9N	R	9W	B-10
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous	S		T	R	
Property in Section	S		T	R	

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 95 OCT 24 PM 4: 13
 REG. OF DEEDS 8723
Lucy J. ...

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kirk Breitels, in a field survey on Sept. 25, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-10 1837 GLO Not Set

No information for this corner

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 9/28/95
 CHAIRMAN *Harry Hubert*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-10 Found nothing at corner. Established intersection of 1/4 lines and found remains of corner fence post for fences E-W-S to be 1' E. & 1' S. ±. Research at Kent Co. Desc. & Mapping turned up a description for a parcel in the Northeast 1/4 of Section 30 that computes back to a Center being the intersection 1/4 lines ±.

The intersection of 1/4 lines is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- B-10 Set Standard Kent County Monument at the intersection of 1/4 lines.
 - Set Nail & KC Remon. tag S. side Tw. 8" Maple S85°E 12.17'
 - Set Nail & KC Remon. tag E. side Tw. 8" Maple S05°W 15.05'
 - Set Nail & KC Remon. tag N. side 12" Cherry N85°W 8.98'
 - Set Nail & KC Remon. tag E. side Tw. 18" Elm N15°W 11.17'



Signed by *Kirk Breitels*
 Surveyor's Michigan License No. 30077

Date 10/20/95