

**SURVEY &
REMONUMENTATION**

MAY 22 2000

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION**

For corners in

SECTION

<u>Kent</u> (County)	Located in: <u>Oakfield</u> Township	Corner Code # <u>C-1</u>
1. Public Land Survey	T <u>9N</u> R <u>9W</u>	<u>C-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REG. OF DEEDS

[Handwritten Signature]

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 DEC - 8 AM 10: 06

11541

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

I, Randy Kolehouse, in a field survey on August 31 19 99, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-1	1837	G.L.O. Notes	Cathcart	Set Post
	1880	Notes	Williams & Works	Fnd. Post / Set Leaded Stone
	1938	Witness Map	K.C. Surveyor	Monument
	1967	Notes	Williams & Works	Set Point
	1984	L.C.R.C. #4005	John Bueche	Fnd. Rerod / Set K.C. Monument
	1992	L.C.R.C. #6427	John Bueche	K.C. Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 10/28/99
CHAIRMAN [Signature]

Note: This corner is not common with C-13, T10N, R9W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by John Bueche on 10/12/84 and was recorded per L.C.R.C. #4005.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-1 Found a Standard Kent County Monument on the C/L of 16 Mile Road (gravel) running East and West, 132' ± West of the C/L of Harvard Avenue (bit.) running North and South, per L.C.R.C.'s #4005 and #6427 as set by John Bueche on the South line of Section.

L.C.R.C. #4005

L.C.R.C. #6427

K.C. Remon. tag & nail in SW side 24" Oak N 50° W 42.42'
K.C. Remon. tag & nail in W. side 8" Pine N 10° E 43.42'
K.C. Remon. tag & nail in SW face 24" Pine N 55° E 85.67'
K.C. Remon. tag & nail in E. side 12" Butternut S 0° E 58.81'
"X" cut in concrete curb return S 75° E 88.31'
Mon. is 5' +/- E. of E. line garg.
C/L E-W gravel road is North 4' +/-

K.C. Remon. Tag & Nail SW side 26" Oak N 50° W 42.42' (m. 42.41')
K.C. Remon. Tag & Nail W side 12" Pine N 10° E 43.35'
K.C. Remon. Tag & Nail SW side 28" Pine N 55° E 85.30' (m. 85.35')
K.C. Remon. Tag & Nail E side 16" Butternut S 00° E 58.81' (m. 58.84')
K.C. Mon. (SW 32, 10-9) East 132.05' (m. 132.06')

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-1 Standard Kent County Monument

Nail & K.C. remon. tag on SW side 26" Oak N 50° W 42.41'
Nail & K.C. remon. tag on W side 12" Pine N 10° E 43.35'
Nail & K.C. remon. tag on SW side 28" Pine N 55° E 85.35'
Nail & K.C. remon. tag on E side 18" Butternut S 00° E 58.84'
"X" cut top curb return S 75° E 88.32'

On C/L of gravel road running E-W
C/L of bit. road running N-S, East 132'
K.C. Mon., C-13, T10N, R9W, East 132.06'

Signed by Randy J. Kolehouse
WILLIAMS & WORKS

Date _____

Surveyor's Michigan License No. 25854

