

MAY 22 2000

\$7.00  
\$2.00

SECTION LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
KENT COUNTY REMONUMENTATION

For corners in

Kent (County)	Located in:	Oakfield Township	Corner Code #
1. Public Land Survey	T <u>9N</u>	R <u>9W</u>	<u>C-12</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

REG. OF DEEDS

*[Signature]*

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
1999 OCT 27 AM 8:36

11415

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Randy Kolehouse, in a field survey on March 10 19 99, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-12	1837	G.L.O. Notes	Cathcart	Set Post
	1942-63	Witness Map	K.C. Surveyor	1 1/2" Pipe
	1975	L.C.R.C. #810	Exxel Engineering	1 1/2" Iron
	1981	L.C.R.C. #1662	Williams & Works	Fnd 1 1/2" Iron / Set K.C. Monument
	1989	L.C.R.C. #5186	John Bueche	K.C. Monument
	1997	L.C.R.C. #9647	Kirk Breitels	K.C. Monument

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Williams & Works on 4/17/81 and was recorded per L.C.R.C. #1662.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-12 Found a Standard Kent County Monument on the C/L of Nugent Avenue (gravel) running North and South and a line of occupation running East per L.C.R.C.'s #1662, #5186, and #9647 as set by Williams & Works in place of a 1-1/2" x 30" iron they found which checked L.C.R.C. #810 and the 1942-63 K.C. Surveyor's records.

L.C.R.C. #1662

L.C.R.C. #9647

Nail and K.C. Remon. tag in W. side 28" Maple N.25°E. 68.53'  
 Nail and K.C. Remon. tag in S. face power pole S.70°W. 48.39'  
 Nail and K.C. Remon. tag in N. face power pole S.80°W. 137.32'  
 Nail and K.C. Remon. tag in W. face 42" Maple S.25°E. 65.80'  
 NW cor. hse. (frame) S.40°E. 110.74'  
 NE cor. hse. (frame) S.40°W. 171.79'  
 Property cor. iron West 33.08'

Nail & KC Remon. tag W. side 52" Maple S25°E 63.72' (m. 63.74')  
 NW cor. hse. (frame) S40°E 110.58' (110.58')  
 NE cor. hse. (frame) S40°W 171.73' (m. 171.77')  
 Nail & KC Remon. tag N. side Power Pole S80°E 137.26' (m. 137.24')  
 Centerline grav. Road North and South

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-12 Standard Kent County Monument

Nail & K.C. remon. tag on W side 52" maple N 25° E 68.62'  
 Nail & K.C. remon. tag on S face P. pole S 70° W 48.37'  
 Nail & K.C. remon. tag on W face 52" maple S 25° E 63.74'  
 Nail & K.C. remon. tag on N side P. pole S 80° E 137.24'  
 NW cor. hse. frame S 40° E 110.58'  
 NE cor. hse. frame S 40° W 171.77'

On C/L of gravel road running N-S  
 On line of occupation running E

Signed by Randy J. Kolehouse Date 10-11-99

WILLIAMS & WORKS

Surveyor's Michigan License No. 25854

