

MAY 22 2000

\$7.00
\$2.00

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

Kent (County)	Located in: Oakfield Township	Corner Code #
1. Public Land Survey	T <u>9N</u> R <u>9W</u>	<u>E-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REG. OF DEEDS

[Signature]

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 DEC - 8 AM 10: 06

11545

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Randy Kolehouse, in a field survey on March 16 19 99, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-1	1837	G.L.O. Notes	Cathcart	Set Post
	1967	Witness Map	K.C. Surveyor	Stone & Iron
	1978	L.C.R.C. #1113	James A. Reda	"T" Iron
	1984	L.C.R.C. #4000	John Bueche	Fnd. "T" Iron, Iron & Stone / Set K.C. Monument
	1992	L.C.R.C. #6429	John Bueche	K.C. Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 10/28/99
CHAIRMAN [Signature]

Note: This corner is not common with E-13, T10N, R9W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by John Bueche on 10/7/84 and was recorded per L.C.R.C. #4000.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-1 Found a Standard Kent County Monument 3.5' ± South of the C/L intersection of 16 Mile Road (gravel) running East and West and Wabasis Avenue (gravel) running North and South per L.C.R.C.'s #4000 and #6429 as set by John Bueche in place of a "T" iron, iron and stone he found on the South line of Section which checked L.C.R.C. #1113 and the K.C. Surveyor's records.

L.C.R.C. #4000

L.C.R.C. #6429

K.C. Remon. tag & nail in SE side 42" Oak N 50° E 45.78'
SE cor. frame hse. N 0° E 82.83'
SW cor. frame hse. N 15° W 84.88'
PK nail SE side 48" Oak N 60° W 88.60'
PK nail SE side utility pole S 70° W 62.50'
C/L E-W gravel road is N 3.5' +/-
On C/L gravel road South

K.C. Remon. Tag & Nail E side 10" Elm in clump S 15° W 92.04' (m. 92.27')
K.C. Remon. Tag & Nail SE side 42" Oak N 50° E 45.78' (m. 45.70')
SE cor. frame hse. N 00° E 82.83' (m. 83.09')
SW cor. frame hse. N 15° W 84.88' (m. 85.00')
PK nail SE side 48" Oak N 60° W 88.60' (m. 88.64')
PK nail SE side utility pole S 70° W 62.50' (m. 62.49')
C: E-W gravel road N 3.5'+/-, on C/L gravel road S
K.C. Mon. (SE 32, 10-9) East 145.00' (m. 145.08')

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-1 Standard Kent County Monument

Nail & K.C. remon. tag on W side 10" Elm S 10° E 101.57'
Nail & K.C. remon. tag on SE side P. pole S 70° W 62.49'
Nail & K.C. remon. tag on SE side 50" Oak N 60° W 88.64'
SW fndn. Cor. hse. N 15° W 85.00'
SE fndn. Cor. hse. N 00° E 83.09'
On C/L of gravel road running N-S

C/L of gravel road running E-W, North 3.5'
K.C. Mon., E-13, T10N, R9W, East 145.08'

Signed by Randy J. Kolehouse

Date 10/29/99

Surveyor's Michigan License No. WILLIAMS & WORKS
25854

