

SURVEY & REMONUMENTATION

\$7.00
\$2.00

MAR 08 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in SECTION

Kent (County)	Located in: Oakfield Township	Corner Code #
1. Public Land Survey	T <u>9N</u> R <u>9W</u>	<u>E-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
38 DEC 14 AM 8:00
REG. OF DEEDS
David Bond

10956

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Randy Kolehouse, in a field survey on January 30 19 98, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-13	1837	G.L.O. Notes	N. Brookfield	Set Post
	1938	Witness Map	K.C. Surveyor	1" Iron
	1975	L.C.R.C. #810	Exxel Engineering	1" Iron in Mon. Box
	1980	L.C.R.C. #1726	Williams & Works	Fnd. 1" iron in Mon. Box / Set K.C. Monument
	1989	L.C.R.C. #5201	John Bueche	K.C. Monument
	1997	L.C.R.C. #9669	Kirk Breitels	K.C. Monument

Note: This corner is not common with E-1, T8N, R9W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Williams & Works on 12/22/80 and was recorded per L.C.R.C. #1726.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-13 Found a Standard Kent County Monument 1' South of the C/L of 10 Mile Road (bit.) running East and West on line of a tree row running North per L.C.R.C.'s #1726, #5201 and #9669 as set by Williams & Works in place of a 1" iron they found in a monument box over a stone down 18" ± which checked L.C.R.C. #810.

L.C.R.C. #1726

L.C.R.C. #9669

K.C. Remon. Tag & Nail in W. Side 12" Hickory N 00°E 72.27'
C/L of 2" Willow N 30°W 63.45'
C/L M.B.T. Box S 05°E 29.92'
"X" Cut on Top of Culvert N 75°W 94.57'
"X" Cut on Top of Culvert n 80°W 117.10'
Iron in Mon. Box N 90°W 72.58'

Nail & KC Remon. tag W side 16" Hickory N 00° E 72.46' (m. 72.44')
Nail & KC Remon. tag E side 22" Willow N 30° W 63.74' (m. 63.75')
Top C/L MBT box S 05° E 29.92'
"X" cut on top of culvert N 75° W 94.57' (m. 94.58')
"X" cut on top of culvert N 80° W 117.14' (m. 117.10')
K.C. Mon. (E-1, T8N, R9W) West 72.60' (m. 72.58')

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13 Standard Kent County Monument in a Monument Box

Nail & K.C. remon. tag on W side 14" Hickory North 72.74'
Nail & K.C. remon. tag on E side 24" Willow N 30° W 63.75'
C/L MBT box S 05° E 29.92'
"X" on top of culvert N 75° W 94.58'
"X" on top of culvert N 80° W 117.70'
Capped iron (10688) N 00° E 33.00'

C/L of bit. road running E-W, North 1'
Tree line North
K.C. Mon., E-1, T8N, R9W, West 72.58'

Signed by Randy J. Kolehouse

Date 11/18/98

Surveyor's Michigan License No. 25854

