

MAY 22 2000

\$7.00
\$2.00

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 DEC 27 AM 8:19

REG. OF DEEDS

[Signature]

11644

Register of Deeds Stamp & File Number

For corners in

Kent (County)	Located in: Oakfield Township	Corner Code #
1. Public Land Survey	T <u>9N</u> R <u>9W</u>	<u>H-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Randy Kolehouse, in a field survey on March 16 19 99, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-6 This corner was not originally set by the G.L.O.

1944--63	Witness Map	K.C. Surveyor	1 1/2" Iron
1978	Cert. Survey L. 79 P. 7	Exxel Engineering	PK Nail
N/A	Records	All Points Surveyors	N/A
1978	L.C.R.C. #1160	Exxel Engineering	PK Nail

P.A. 345 1990 KENT COUNTY
PEER APPROVED 7/29/99
CHAIRMAN [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-6 Found a PK nail 2' ± East of the C/L intersection of Podunk Avenue (bit.) running North and South and Stultz Street (gravel) running West, on line of a tree row running East, per L.C.R.C. #1160, the records of All Points Surveyors, Cert. Survey L. 79 P. 7, and the K.C. Surveyor's records. The PK nail is 11.8' South 10.2' West of the intersection of 1/4 lines. Accepted PK nail as Center of Section.

L.C.R.C. #1160 & Cert. Survey L. 79 P. 7

- NE cor hse W-SW 92.53' (m. 92.38')
- Spike in sde 18" Locust ENE 52.58' (m. 52.70')
- Spike in sde 20" Locust NNE 80.49' (m. 80.48')
- Spike in sde 6" Wild Cherry NW 62.73' (m. 62.60')

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-6 Replaced PK Nail with a Standard Kent County Monument -- Also Set a Monument Box

- Nail & K.C. remon. tag on S side 24" Locust N 85° E 52.37'
- Nail & K.C. remon. tag on SE side 26" Locust N 35° E 80.48'
- Nail & K.C. remon. tag on E side twin 8" Elm N 15° W 88.80'
- Nail & K.C. remon. tag on SE side twin 12" Cherry N 45° W 62.60'
- NE cor. hse. fndn. #11201 S 40° W 92.38'
- C/L "X" of gravel road running W and bit. road running N-S, West 2' ±
- On tree row running E



Signed by Randy J. Kolehouse Date 12-20-99

WILLIAMS & WORKS

Surveyor's Michigan License No. 25854