

SURVEY & REMONUMENTATION

\$7.00
\$2.00

MAR 08 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

SECTION

Kent (County)	Located in:	Oakfield Township	Corner Code #
1. Public Land Survey	T <u>9N</u> R <u>9W</u>		<u>H-13</u>
	T _____ R _____		_____
	T _____ R _____		_____
	T _____ R _____		_____
2. Property Controlling in Section	S _____ T _____ R _____		_____
	S _____ T _____ R _____		_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		_____
	S _____ T _____ R _____		_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
38 DEC 14 AM 8:00
REG. OF DEEDS
Luigi Standa

10957

Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on January 30 19 98, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-13	1837	G.L.O. Notes	N. Brookfield	Set Post
	1965-77	Notes	Williams & Works	"T" Iron
	1980	L.C.R.C. #3329	Glaza & Associates	"T" Iron
	1985	L.C.R.C. #4118	William Byl	Fnd. "T" Iron / Set K.C. Monument
	1994	L.C.R.C. #7213	Glaza & Associates	K.C. Monument

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

P.A. 345 1990 KENT COUNTY
PEER APPROVED 9/24/98
CHAIRMAN Harry Stube

Note: This corner is not common with H-1, T8N, R9W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by William Byl on 11/5/84 and was recorded per L.C.R.C. #4118.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13 Found a Standard Kent County Monument 4' North of a fence line running East and 170' ± East of the C/L of McArthur Avenue (gravel) running North and South per L.C.R.C.'s #4118 and #7213 as set by William Byl in place of a "T" iron he found which checked L.C.R.C. #3329 and the 1965-77 notes of Williams & Works.

L.C.R.C. #4418	L.C.R.C. #7213
Nail & tag, W sd. Trip. 18" Hickory S 45 E 75.37'	Nail & K.C. remon tag in W side 18" Triple Hickory S45°E 75.37'
Nail & tag, S sd. 12" Hickory N 80 E 31.80'	Nail & K.C. remon tag in S side 14" Hickory N80°E 31.85'
Nail & tag, E sd. 8" Oak N 30 W 44.13'	Nail & K.C. remon tag in E side 12" Oak N30°W 44.15'
East-West fence S 00 E 4.4'	East-West fence S00°E 4.40'
	Kent Co. Mon (N 1/4 cor, Sec 3, T8N, R9W) N90°W 170.68' (m. 170.69')

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13 Standard Kent County Monument
Nail & K.C. remon. tag on W side 18" triple Hickory S 45° E 75.37'
Nail & K.C. remon. tag on S side 14" Hickory N 80° E 31.85'
Nail & K.C. remon. tag on E side 12" Oak N 30° W 44.15'
Nail & K.C. remon. tag on N side 12" Cherry N 90° W 31.98'
Fence line running E, South 4'
C/L of gravel road running N-S, West 170' ±
K.C. Mon., H-1, T8N, R9W, N 90° W 170.69'



Signed by Randy J. Kolehouse Date 11/18/98
EARTH TECH

Surveyor's Michigan License No. 25854