



MAY 22 2000

C/L of (bit.) road running N-S, West 2

Surveyor's Michigan License No.

WILLIAMS & WORKS

LAND CORNER RECORDATION CERTIFICATE SECTION Filing Requirement of Act 74, Mich. P.A. 1970 For corners in KENT COUNTY REMONUMENTATION Oakfield Corner Code # Located in: Ken (County) Township **Public Land Survey** R 9W 2 **Property Controlling** 11564in Section 3 Miscellaneous Register of Deeds Stamp & File Number Property in Sec. , Recorded Plat **Private Claims** in a field survey on Randy Kolehouse August 19 do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below: NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate. A. Description of original monument and accessories and/or subsequent restoration: P.A. 345 1990 KENT COUNTY PEER APPROVED 10/26 1837 G.L.O. Notes 1-3 Cathcart Set Post K.C. Surveyor N/A Witness Map Stone & Crockery 1979 L.C.R.C. #1275 John Merdzinski Boat Spike in Mon. Box 1981 L.C.R.C. #1663 Williams & Works Fnd. Boat Spike & Iron / Set K.C. Monument in Mon. Box 1994 L.C.R.C. #7216 Glaza & Associates K.C. Monument This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Williams & Works on 4/16/81 and was recorded per L.C.R.C. #1663. В. Description of corner evidence found and/or method applied in restoring or reestablishing corner: Found a Standard Kent County Monument 2' ± East of the C/L intersection of Lincoln Lake Avenue (bit.) running North and South and Stacey Street (gravel) running East per L.C.R.C.'s #1663 and #7216 as set by Williams & Works in place of a boat spike they found on top of a 1" x 18" iron which checked L.C.R.C. #1275 and the K.C. Surveyor's records. LCRC #1663 L.C.R.C. #7216 Center line top tel. Box S.19°E. 52.49' Centerline top telephone Box S19°E 52.45' (m. 52.44') K.C. Remon. tag in W side 12" Cedar S.5°E. 201.89' K.C. remon tag & nail in W side 34" Cedar S05°E 201.90' K.C. Remon. tag in S side Power Pole N.70°E. 70.35' Centerline Lincoln Lake Ave (asphalt) N & S - West 2.2', Center line Lincoln Lake Ave. (asphalt) N & S on centerline Stacey (gravel) East West 2.2', on center line Stacey (gravel) East K.C. remon tag & nail in NW side P. pole N50°E 70.49' (m. 70.53') East face of South leg of road sign N80°W 26.65' (m. 26.70') The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner. C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: 1.3 Standard Kent County Monument C/L top telephone box S 19° E 52.44' Nail & K.C. remon. tag on W face 34" Cedar S 05° E 201.90' Nail & K.C. remon. tag on NW face P. pole N 50° E 70.53' KOLEHOUSE E face of S road sign N 80° W 26.70' On C/L of gravel road running E