

MAY 22 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

SECTION
For corners in Kent (County)

Table with columns: Located in: Oakfield Township, Corner Code #, and rows for Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec., Lot No., and Private Claims.

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 OCT 27 AM 8:39
REG. OF DEEDS

11448

Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on February 24, 1999, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
J-1 This corner was not originally set by the G.L.O.

1934 Witness Map K.C. Surveyor 1" Iron
1989 L.C.R.C. #5161 John Bueche Fnd. Iron - Set K.C. Monument
1997 L.C.R.C. #9984 Kirk Breitels K.C. Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 7/29/99
CHAIRMAN [Signature]

Note: This corner is not common with J-13, T10N, R9W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by John Bueche on 5/22/89 and was recorded per L.C.R.C. #5161.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-1 Found a Standard Kent County Monument on the C/L of 16 Mile Road (bit.) extended East and 51' + West of the West edge of the water, 23' ± South of a fence line running East and West per L.C.R.C.'s #5161 and #9984 as set by John Bueche next to a solid iron, he found which checked the K.C. Surveyor's records.

L.C.R.C. #5161

L.C.R.C. #9984

K.C. Remon. Tag & Nail in E side 10" Sassafras N 0° E 22.69'
K.C. Remon. Tag & Nail in E side 16" Oak N 35° W 25.23'
K.C. Remon. Tag & Nail in SW side 20" Oak N 65° W 35.42'
K.C. Remon. Tag & Nail in N side 18" Oak S 55° E 33.35'
K.C. Mon. (J-13 10-9) East 64.78'
Edge of Lake East 67'+/-

Nail & KC Remon. tag E. side 12" Sassafras N00°E 22.76' (m. 22.74')
Nail & KC Remon. tag E. side 18" Oak N35°W 25.19' (m. 25.18')
Nail & KC Remon. tag SW side 22" Oak N65°W 35.39' (m. 35.32')
Nail & KC Remon. tag W. side 18" Oak S55°E 33.56' (m. 33.20')
Nail & KC Remon. tag W. cor. of S. guard rail post S20°W 35.15' (m. 35.18')
KC Mon. (J-13, 10-9 at edge of lake-unstable) East 64.78' (m. 51.5')

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
J-1 Standard Kent County Monument

Nail & K.C. remon. tag on E side 12" Sassafras N 00° E 22.74'
Nail & K.C. remon. tag on E side 18" Oak N-35° W 25.18'
Nail & K.C. remon. tag on SW side 22" Oak N 65° W 35.32'
Nail & K.C. remon. tag on W side 18" Oak S 55° E 33.20'
Nail & K.C. remon. tag on W cor. of S guard rail post S 35° W 35.18'
On C/L of bit. road extended E
West edge of water, East 51' ±
Fence line running E-W, North 23' ±
K.C. Mon., J-13, T10N, R9W, East 64.78'



Signed by [Signature] Date 10-11-99
WILLIAMS & WORKS
Surveyor's Michigan License No. 25854