

MAY 22 2000

\$7.00  
\$2.00

SECTION \_\_\_\_\_

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970  
KENT COUNTY REMONUMENTATION

For corners in

| Kent<br>(County)                      | Located in: Oakfield<br>Township | Corner Code # |
|---------------------------------------|----------------------------------|---------------|
| 1. Public Land Survey                 | T <u>9N</u> R <u>9W</u>          | <u>L-1</u>    |
|                                       | T _____ R _____                  | _____         |
|                                       | T _____ R _____                  | _____         |
|                                       | T _____ R _____                  | _____         |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____          | _____         |
|                                       | S _____ T _____ R _____          | _____         |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____          | _____         |
|                                       | S _____ T _____ R _____          | _____         |

REG. OF DEEDS

*[Signature]*

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
1999 DEC - 8 AM 10:10

11573

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

|    |    |    |    |    |    |    |   |   |   |   |   |   |   |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
| 2  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 13 | 14 | 15 | 16 | 17 | 18 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 25 | 26 | 27 | 28 | 29 | 30 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

I, Randy Kolehouse, in a field survey on March 16 19 99, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

L-1 This corner was not originally set by the G.L.O.

|      |                |                    |  |
|------|----------------|--------------------|--|
| 1938 | Witness Map    | K.C. Surveyor      | Monument   |
| 1981 | L.C.R.C. #2098 | Medema, Van Kooten | "T" Iron   |
| 1984 | L.C.R.C. #4008 | John Bueche        | Fnd. "T" Iron & Conc. Monument / Set K.C. Monument |
| 1989 | L.C.R.C. #5073 | John Bueche        | K.C. Monument                                      |
| 1997 | L.C.R.C. #9986 | Kirk Breitels      | K.C. Monument                                      |

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 10/29/99  
CHAIRMAN [Signature]

Note: This corner is not common with L-13, T10N, R9W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by John Bueche on 10/11/84 and was recorded per L.C.R.C. #4008.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-1 Found a Standard Kent County Monument on the C/L of 16 Mile Road (bit.) running East and West per L.C.R.C.'s #4008, #5073, and #9986 as set by John Bueche in place of a "T" iron he found on the South line of Section 36 over a concrete monument which checked L.C.R.C. #2098 and the K.C. Surveyor's records.

L.C.R.C. #4008

L.C.R.C. #9986

K.C. Remon. tag & nail in S. side 16" Pine N 50° W 54.56'  
K.C. Remon. tag & nail in W. side dbl. 24" Oak N 25° E 38.85'  
K.C. Remon. tag & nail in W. side 10" Pine N 60° E 75.31'  
K.C. Remon. tag & nail in W. side 12" Oak S 5° E 40.17'  
K.C. Remon. tag & nail in W. side 12" Oak S 50° E 68.30'  
Cut nail in E. side 10" Pine S 50° W 52.74'  
On C/L blacktop road E-W

Nail & KC Remon. tag S. side 18" stump N50°W 54.52' (m. 54.57')  
Nail & KC Remon. tag W. side dbl. 26" Oak N25°E 38.85' (m. 38.87')  
Nail & KC Remon. tag W. side 16" Pine N60°E 75.31' (m. 75.30')  
Nail & KC Remon. tag W. side 16" Oak S05°E 40.15' (m. 40.17')  
Nail & KC Remon. tag W. side 16" Oak S50°E 68.27' (m. 68.26')  
Nail & KC Remon. tag E. side 16" Pine S50°W 52.80' (m. 52.78')  
K.C. Mon. L-13, T10N, R9W East 13.83' (m. 13.85')

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-1 Standard Kent County Monument

Nail & K.C. remon. tag on S side 18" stump N 50° W 54.57'  
Nail & K.C. remon. tag on W side dbl. 26" Oak N 25° E 38.87'  
Nail & K.C. remon. tag on W side 16" Pine N 60° E 75.30'  
Nail & K.C. remon. tag on W side 16" Oak S 05° E 40.17'  
Nail & K.C. remon. tag on W side 16" Oak S 50° E 68.26'  
Nail & K.C. remon. tag on E side 16" Pine S 50° W 52.78'

On C/L of bit. road running E-W  
K.C. Mon., L-13, T10N, R9W, East 13.85'

Signed by Randy J. Kolehouse Date 10/29/99

WILLIAMS & WORKS

Surveyor's Michigan License No. 25854

