

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

MAY 22 2000

Kent (County)	SECTION	Located in: Oakfield Township	Corner Code #
1. Public Land Survey	T 9N	R 9W	M-2
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

REG. OF DEEDS

[Signature]

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 1999 DEC - 8 AM 10:10

11577

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Randy Kolehouse in a field survey on September 27 19 99, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-2	1837	G.L.O. Notes	Cathcart	Set Post
	1979	L.C.R.C. #1264	Glaza & Associates	Iron Rod
	1980	L.C.R.C. L. 1 P. 518	Montcalm County	Rerod on Town Line
	1987	L.C.R.C. #4532	John Bueche	Fnd. Rerod / Set K.C. Monument
	1994	L.C.R.C. #7255	Glaza & Associates	K.C. Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 10/29/99
 CHAIRMAN [Signature]

Note: This corner is common with A-2, T9N, R8W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by John Bueche on 12/7/87 and was recorded per L.C.R.C. #4532.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-2 Found a Standard Kent County Monument 2' ± North of MacClain Street (bit.) running West and 4' ± West of Montcalm Avenue (bit.) running North and South per L.C.R.C. #4532 and #7255 as set by John Bueche in place of a rerod he found which checked L.C.R.C. #1264 and L.C.R.C. L. 1 P. 518 (Montcalm County).

L.C.R.C. #4532

L.C.R.C. #7255

K.C. remon. tag & nail in SE side power pole S 30° W 83.14'
 K.C. remon. tag & nail in E side 30" Walnut N 35° W 59.30'
 K.C. remon. tag & nail in S side 8" Walnut S 70° E 35.65'
 K.C. remon. tag & nail in SW side 16" Walnut S 45° E 59.79'
 K.C. remon. tag & nail in W side 8" Walnut N 30° E 68.49'
 2' +/- N C/L road W., 4' +/- N. of C/L road N-S

K.C. remon tag & nail in SE side P. pole S30°W 83.14' (m. 83.17')
 K.C. remon tag & nail in E side 30" Walnut N35°W 59.27' (m. 59.22')
 K.C. remon tag & nail in S side 10" Walnut S70°E 35.70' (m. 35.80')
 K.C. remon tag & nail in SW side 18" Walnut S45°E 59.79' (m. 60.09')
 K.C. remon. tag & nail in W side 14" Walnut N30°E 68.44' (m. 68.36')
 2' +/- N C/L road W, 4' +/- N of C/L road N-S

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-2 Standard Kent County Monument

Nail & K.C. remon. tag on SE side P. pole S 30° W 83.17'
 Nail & K.C. remon. tag on E side 30" Walnut N 35° W 59.22'
 Nail & K.C. remon. tag on S side 10" Walnut S 70° E 35.80'
 *Nail & K.C. remon. tag on SW side 16" Walnut S 45° E 60.09'
 Nail & K.C. remon. tag on W side 10" Walnut N 30° E 68.36'
 C/L of bit. road running W, South 2' ±
 C/L of bit. road running N-S, East 4' ±

Signed by [Signature] Date _____

WILLIAMS & WORKS

Surveyor's Michigan License No. 25854

