

MAY 22 2000

\$7.00  
\$2.00

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
1999 DEC - 8 AM 10:10

REG. OF DEEDS

11578

Register of Deeds Stamp & File Number

For corners in

Kent  
(County)

Located in: Oakfield  
Township

Corner Code #

1. Public Land Survey	T <u>9N</u>	R <u>9W</u>	<u>M-3</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Randy Kolehouse, in a field survey on September 27 19 99, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A.	Description of original monument and accessories and/or subsequent restoration:
M-3	1837 G.L.O. Notes Cathcart Set Post
	1980 L.C.R.C. L. 1 P. 518 Montcalm County Fnd. Stone / Set Rerod
	1987 L.C.R.C. #4535 John Bueche Fnd. Iron & Stone / Set K.C. Monument
	1994 L.C.R.C. #7256 Glaza & Associates K.C. Monument

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	16	17	18	19	20	21					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 10/28/99  
CHAIRMAN Randy Kolehouse

Note: This corner is common with A-3, T9N, R8W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by John Bueche on 3/26/86 and was recorded per L.C.R.C. #4535.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
M-3 Found a Standard Kent County Monument 2' ± West of the C/L of Montcalm Avenue (gravel) running North and South, on line of a tree row running West, per L.C.R.C.'s #4535 and #7256 as set by John Bueche in place of an iron and stone he found per L.C.R.C. L. 1 P. 518 (Montcalm County).

L.C.R.C. #4535

L.C.R.C. #7256

K.C. remon. tag & nail in S. side 18" Cherry N 85° W 48.25'  
K.C. remon. tag & nail in S. side Twin 30" Oak N 80° W 25.19'  
K.C. remon. tag & nail in SE side 16" Oak S 40° W 40.09'  
1/2" x 18" rerod S 80° E 33.16'  
K.C. remon. tag & nail in NE side 30" Maple S 35° E 42.30'  
2' W. of centerline gravel road N-S

K.C. remon tag & nail in S side 18" Cherry N85°W (m. 48.08')  
K.C. remon tag & nail in S side 30" Twin Oak N80°W 25.21' (m. 25.20')  
K.C. remon tag & nail in SE side 18" Oak S40°W 40.09' (m. 40.08')  
1/4" x 18" rerod S80°E 33.12' (m. 33.15')  
K.C. remon tag & nail in NE side 27" Oak S35°E 42.25" (m. 42.19')  
In centerline of gravel road

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
M-3 Standard Kent County Monument  
Nail & K.C. remon. tag on S side 20" Cherry N 85° W 48.08'  
Nail & K.C. remon. tag on S side twin 32" Oak N 80° W 25.20'  
Nail & K.C. remon. tag on SE side 18" Oak S 40° W 40.08'  
Nail & K.C. remon. tag on NE side 32" Oak S 35° E 42.19'  
Nail & K.C. remon. tag on S side 40" Oak S 80° E 30.03'  
Rerod East 33.15'  
C/L of gravel road running N-S, East 2' ±  
On tree row running W



Signed by Randy J. Kolehouse Date 10-29-99

Surveyor's Michigan License No. 25854