

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970 KENT COUNTY REMONUMENTATION

For corners	ın
-------------	----

Private Claims

SECTION

, Recorded Plat

<u>Kent</u>	Located in: Oa	kfield Corner Code #			
(County)	Tow	Township			
Public Land Survey	T <u>9N</u> R <u>9V</u>	<u>M-5</u>			
	T R				
	T R				
	T R				
Property Controlling					
· · ·	· · · · · · · · · · · · · · · · · · ·				
in Section	S R				
Miscellaneous	S T R				
Property in Sec.	S R				
	(County) Public Land Survey Property Controlling In Section Miscellaneous	(County) Tow Public Land Survey T 9N R 9N T R T R T R T R T R T R T R T R T R T			

11668 Register of Deeds Stamp & File Number

I, Randy Kolehouse,	in a field survey on	luk 16		19	00
do hereby certify that under requ	irements of P.A.	74 Michigan P.A.	of 1970, the	corner	points
mentioned in lines 1 and 2 above	were in conform	ance with regulati	ons and rule:	s therefo	re as
required in the current manual of si	urvey instructions o	of the United States	s Department	of the in	terior,
Bureau of Land Management or by	decree of a Court	of Law and/or that	the corner po	ints men	tioned
in lines 3, 4 and 5 above were in col	ntormance with the	rules of the Michig	an Board of L	and Surv	eyors
or by a Decree of a Court of La recovered, found as expressed below	w, established, i W:	e-established, mo	numented, re	-monume	ented,

Not more than 4 corners, all in the same town and range, may be recorded NOTE: on this certificate.

Description of original monument and accessories and/or subsequent restoration:

M-5 1837 G.L.O. Notes N/A Witness Map 1983 L.C.R.C. #3325 1984 L.C.R.C. #3720 Cathcart K.C. Surveyor Glaza & Associates All-Points Surveyors

Stone 1" Iron in Mon. Box Iron in Mon. Box

Set Post

P.A. 345 1990 KENT COUN PEER APPROVED 7/29

1984 L.C.R.C. #3734 Williams & Works

Fnd. Bt. Spike / Set K.C. Monument in Mon. Box

Note: This corner is common with A-5, T9N, R8W.

This comer was originally approved by the Kent County Remonumentation Peer Group and monumented by Williams & Works on 2/2/84 and was recorded per L.C.R.C. #3734.

Description of corner evidence found and/or method applied in restoring or reestablishing corner: R.

M-5 Found a Standard Kent County Monument on the C/L of Montcalm Road (gravel) running North and South per L.C.R.C. #3734 as set by Williams & Works in place of a 1" boat spike they found which checked L.C.R.C.'s #3720, #3325 and the K.C. Surveyor's records.

L.C.R.C. #3734

Nail & KC Remon.tag in SWly face CTV pole N.70°W. 69.53' (m. 69.60') C/L flag pole S.48°E. 91.25' (m. 91.32')

Frame corner to house S.30°W. 137.55' (m. 137.57')

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Description of monument for corner and accessories established to perpetuate locating the position of the corner: C.

M-5 Standard Kent County Monument

> Nail & K.C. remon. tag on SWly face CTV pole N 70° W 69.60' C/L flag pole S 48° E 91.32' Frame cor. to hse. S 30° W 137.57' NW cor. attached garage S 40° E 160.75' On C/L of gravel road running N-S

Signed by

WILLIAMS & WORKS

Surveyor's Michigan License No. 25854

RANDY J. KOLEHOUSE LAND SED LAND

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS REVISED MAY 14, REVISED JAN.,