

\$7.00
\$2.00

MAY 22 2000

SECTION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

Kent (County)	Located in: Oakfield Township	Corner Code #
1. Public Land Survey	T <u>9N</u> R <u>9W</u>	<u>M-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REG. OF DEEDS

[Signature]

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 DEC 27 AM 8:20

11671

Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on July 15 19 99, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-8	1837	G.L.O. Notes	Cathcart	Set Post
	1913	Notes	Williams & Works	Set Iron
	1950	Notes	Williams & Works	Set Temporary Point
	1983	L.C.R.C. #3589	William Byl	Iron Pipe
	1984	L.C.R.C. #3943	William Byl	Fnd. Iron Pipe / Set K.C. Monument
	1994	L.C.R.C. #7261	Glaza & Associates	K.C. Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 7/29/99

CHAIRMAN [Signature]

Note: This corner is common with A-8, T9N, R8W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by William Byl on 9/20/84 and was recorded per L.C.R.C. #3943.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-8 Found a Standard Kent County Monument on line of a downed fence line running North and 80' ± North of the North edge of County Line Lake per L.C.R.C.'s #3943 and #7261 as set by William Byl in place of an iron pipe he found which checked L.C.R.C. #3589.

L.C.R.C. #3943

L.C.R.C. #7261

Nail & tag, W. sd. 20" Oak N 05 E 47.11'

Nail & tag, S. sd. 30" Oak N 60 E 15.96'

Nail & tag, W. sd. 12" Oak S 25 E 35.57'

Nail & tag, E. sd. 12" Oak S 35 W 24.26'

Nail & tag, S. sd. 15" Trip. Maple N 85 W 38.40'

Nail & tag, S. sd. 24" Twin Maple N 8 W 6.06'

North side of County Line Lake S 00 W 80'

Nail & K.C. remon tag in W side 14" Oak N05°E 47.00'

Nail & K.C. remon tag in S side 29" Oak N60°E 15.96' (m. 16.00')

Nail & K.C. remon tag in W side 12" Oak S25°E 35.62' (m. 35.80')

Nail & K.C. remon tag in E side 14" Oak S35°W 24.26' (m. 24.41')

Nail & K.C. remon tag in S side 12" Triple Maple N85°W 38.40' (m. 38.45')

Nail & K.C. remon tag in S side 24" Twin Maple N80°W 6.06' (m. 6.05')

North side of County Line Lake S00°W 80'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-8 Standard Kent County Monument

Nail & K.C. remon. tag on W side 16" Oak N 05° E 47.00'

Nail & K.C. remon. tag on S side 29" Oak N 60° E 16.00'

Nail & K.C. remon. tag on W side 14" Oak S 25° E 35.80'

Nail & K.C. remon. tag on E side 16" Oak S 35° W 24.41'

Nail & K.C. remon. tag on S side 12" triple Maple N 85° W 38.45'

Nail & K.C. remon. tag on S side 26" twin Maple N 80° W 6.05'

North edge of lake, South 80' ±

On downed fence line running N



Signed by [Signature]

Date 10-22-99

WILLIAMS & WORKS

Surveyor's Michigan License No. 25854